

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


Company- WILKINSON DRILLING, INC.  
Farm- Harkness No. 1

SEC. 11 T. 24 R. 15W  
SW SW NW

Total Depth. 4050'  
Comm. 4-28-60 Comp. 5-8-60

County Stafford  
KANSAS

Shot or Treated.  
Contractor. Wilkinson Drilling, Inc.  
Issued. 8-13-60



CASING:

8 5/8" @ 220' w/185 sks. cem.  
4 1/2" @ 4049' w/175 sks. cem.

Elevation. 2018'

Production. 3,000 BOPD

Figures indicate Bottom of Formations.

sand, shale & shells	220
shale, shells & red bed	933
Anhydrite	955
shale & shells	1760
shale & lime	1925
lime & shale	2075
lime	2265
lime & shale	2390
shale & lime	2525
lime & shale	3469
shale	3475
lime	3480
shale	3488
lime	3512
shale	3606
lime & shale strks.	3966
vari-colored shale & chert	3979
chert	3993
shale & sand	4022
Arbuckle dolomite	4050
Total Depth	

SCOUT TOPS:

Heebner	3496
Douglas	3512
Brown Lime	3606
Lansing	3614
Base Kansas City	3917
Conglomerate	3966
Viola	3979
Simpson	3993
Arbuckle	4022