


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- GREENLAND DRILLING CO., ET AL
Farm- English No. 2

SEC. 13 T. 24 R. 15W
SE NW NW

Total Depth. 4242
Comm. 7-21-54 Comp. 7-30-54
Shot or Treated.
Contractor. Greenland Drilling Co.
Issued. 8-7-54

County Stafford
KANSAS



CASING:

Elevation. 2007 DF

8 5/8" 214' cem. w/225 sx

Production. dry

Figures indicate Bottom of Formations.

sand & clay	120
shale & shells	280
redbed w/sd stks.	952
Anhydrite	973
shale & shells	1310
shale & shells w/salt	1620
shale & shals	1785
lime & shale	2035
lime	2112
lime & shale	2985
lime & shale w/silt	3145
lime w/sh. brks	3230
lime & shale	3310
silt, shale & lime	3440
lime w/sh. brks	3525
lime & shale	3548
Heb. shale	3552
lime & shale	3618
shale & sand	3705
Brn lime & sand	3716
Lansing	3723
lime	4026
lime & shale	4098
Conglomerate	4140
Viola	4152
lime & shale	4169
lime & shale w/chert	4205
Viola chert	4242
Total depth	

Tops:

Heebner	3564
Toronto	3583
Douglas	3600
Br. lime	3705
Lansing	3717
Conglomerate	4100
Miss.	4129
Kinderhook	4145
Maquoketa	4157
Viola	4167