


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GREENLAND DRILLING CO. & NCRA
Farm- Isern No. 1

SEC. 14 T. 24 R. 15W
NE NE NE

Total Depth. 4270
Comm. 3-17-54 Comp. 3-30-54
Shot or Treated.
Contractor. Greenland Drilling Co.
Issued. 12-24-55

County Stafford
KANSAS



CASING:

8 5/8 215' w/ 207 sx cmt.
5 1/2 @ 4252' w/ 125 sx cmt.

Elevation. 2005 DF

Production Flow 324 BOPD

Figures indicate Bottom of Formations.

top soil	25
sand	45
sand, clay & shells	120
shale & shells	425
red bed	954
anhydrite	972
shale & shells	1250
shale & shells w/ salt	1778
lime & shale	3347
lime & shale w/ salt	3480
lime	3524
lime & shale	3534
shale & sandy shale	3587
sandy shale	3676
brown lime	3682
shale	3687
Lansing lime	3688
lime	3897
lime & shale	3957
shale & lime w/ chert	4012
shale & lime	4059
shale & lime w/ chert	4106
conglomerate	4120
Viola chert	4152
chert	4157
Arbuckle	4270
Total Depth	

TOPS:

Heebner	3534
Brown lime	3676
Lansing	3687
Viola	4086
Simpson	4156
Arbuckle	4239

DST #1: 4089-4159, open 1 hr. gas to
surf. 11 min. flowed oil into pits
in 1 hr. IFP 210#, FFP 1075#, BHP
1325#/15 min.