


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HARMS-BURT DRILLING CO.
Farm- DeBusk No. 1

SEC. 24 T. 24 R. 15W
NW NW NE

Total Depth. 4400
Comm. 8-23-54 Comp. 9-7-54
Shot or Treated.
Contractor.
Issued. 4-2-55

County Stafford
KANSAS



CASING:
8 5/8" 210' cem w/250 sx

Elevation. 2009 RB

Production. dry

Figures indicate Bottom of Formations

clay, sand	30
sand	150
shale, shells	285
red bed, shells	415
red bed, sand	480
red bed, shells	945
anhydrite	965
shale, shells	1350
shale, shells, salt	1804
lime, shale	1910
lime	1975
lime, shale	2120
lime	2220
lime, shale	3090
lime,	3105
lime, shale	3265
lime	3450
lime, shale	3600
lime	3645
lime, shale	3745
lime	4020
lime, shale	4132
lime, shale, chert	4156
congl. cherty	4207
chert, lime	4235
congl. cherty	4252
chert, lime	4272
lime	4275
lime sdy, green shale	4296
sand	4315
lime, shale	4328
sand	4336
lime, shale	4344
lime	4400
Total Depth	

Tops:
Anhydrite 945
Heebner (Scout) 3556
Lansing 3600
Viola 4252
Simpson sand 4296
Arbuckle 4348

DST #1 4297-4315 Open
1 hr. Shut in 20 mins.
7' drlg mud. IFP 5#
FFP 5# BHP 30#.