


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - J.D. FERRELL DRIG. & CROWN OIL COS. SEC. 27 T. 24 R. 15W  
Farm - Campbell "B" No. 1 SW SW NW

Total Depth. 4325'  
Comm. 4-18-49 Comp. 6-28-49  
Shot or Treated.  
Contractor. J. D. Ferrell Drig.  
Issued. 8-13-49

County. Stafford  
KANSAS



CASING:  
8" 415  
5" 4250

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

|                     |                    |
|---------------------|--------------------|
| cellar              | 6                  |
| clay                | 32                 |
| sand                | 110                |
| shale & shells      | 305                |
| sand                | 335                |
| shale               | 375                |
| shale & shells      | 385                |
| red bed & shells    | 495                |
| shale & shells      | 580                |
| red bed & shale     | 960                |
| shale               | 1020               |
| anhydrite           | 1275               |
| shale & shells      | 1575               |
| sand & shale        | 1775               |
| shale & lime        | 1975               |
| lime                | 2 130              |
| lime & shale        | 2 520              |
| lime                | 2 650              |
| lime & shale        | 3809               |
| lime                | 3870               |
| lime & shale        | 3905               |
| lime                | 4073               |
| lime & shale        | 4163               |
| conglomerate        | 4203               |
| lime, cherty        | 4206               |
| Mississippi         | 4230               |
| sand & shale        | 4240               |
| chert RTD           | 4246               |
| shale               | 4248               |
| shale brwn          | 4251               |
| shale brwn sdy      | 4256               |
| shale brwn sdy      | 4261               |
| shale sdy gy        | 4267               |
| shale sdy           | 4292               |
| lime                | 4 295              |
| shale & lime        | 4303 $\frac{1}{2}$ |
| shale brwn          | 4307               |
| shale red & brwn    | 4310               |
| shale & lime shells | 4316               |
| lime cherty         | 4325               |
| Total Depth         |                    |

|                  |      |
|------------------|------|
| Tops:            |      |
| Heebner          | 3644 |
| Kansas City      | 3801 |
| Base K. C.       | 4177 |
| Mississippi      | 4206 |
| Kinderhook Shale | 4225 |
| Kinderhook sand  | 4230 |