

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


60077

Company - SUPERIOR OIL CO.
Farm - Addie Campbell No. 1.

SEC. 27 T. 24 R. 15 W
SW SE SW

Total Depth. 4517' PB 4087'
Comm. 2-26-44 Comp. 5-2-44
Shot or Treated. 20 Qts. NitroGly. 4232-41
Contractor.
Issued. 5-27-44

County. Stafford
KANSAS



CASING:

10 3/4" 1006'
7" 4230'

Elevation. _____

Production. 8,506,000 M.G.

Figures Indicate Bottom of Formations.

surface clay & sand	180
shale & shells	195
shale & sand	370
red bed	420
lime	425
red bed shells & shale	990
anhydrite	1036
shale & shells	1485
salt, shale, & shells	1600
sandy shale	1925
lime & shale	1985
gray shale	2080
lime	2095
sandy lime	2165
lime	2255
shale & shells	2405
lime	2520
shale	2550
lime	2650
broken lime	2765
lime	2835
shale	2875
shale & lime	2895
lime	2935
dark shale	3035
broken lime & lime	3120
shale	3180
broken lime	3270
dark shale	3320
lime	3430
lime	3515
shale	3530
shale dark	3570
lime broken & hard	3655
shale	3675
lime	3690
shale black	3820
lime	3840
shale	3848
lime broken hard	3985
lime & shale	4010
broken lime rough	4095
shale red & gray	4105
broken lime	4165
shale & shells	4209
chert & lime	4240
sandy shale	4265
shale	4300
shale & chert	4360
chert & lime	4400
lime	4413
Simpson shale	4420
sand	4429
shale, sdy shale	4475
green shale	4480
shale	4487
Arbuckle lime	4517
Total Depth	

Tops:

Brown Lime	3786
Lansing	3797
B. Kans. City	4166
Cherty Cg.	4198
Sand	4230
Viola	4306
Simpson Sh.	4413 ✓
Arbuckle	4480 ✓

Plugged back 4087