


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **ANSCHUTZ DRILLING CO., INC.**
 Farm- **Ackerman** No. **1**

SEC. **29** T. **24** R**15W**
 NW NW SW

Total Depth. **4505**
 Comm. **8-9-56** Comp. **8-24-56**
 Shot or Treated.
 Contractor.
 Issued. **11-3-56**

County **Stafford**
KANSAS



CASING:
8 5/8" 223' cem w/175 sx.
5 1/2" 4300' cem w/150 sx.

Elevation. **2045 D.F.**

Production. **88 bbls**

Figures Indicate Bottom of Formations.

shale, shells	255	1,350 M - 75 Mins.
shale	1000	1,250 M - 80 "
red bed	1012	1,140 M - 85 "
anhydrite	1040	1,140 M - 90 "
shale	1300	1,020 M - 95 "
shale, shells	1900	1,020 M -100 "
lime, shale	3845	953 M -105 "
lime	3915	Recovered 60' gas cut mud. IF 1440#, FP 500#, BHP
lime, shale	3969	670#/30 mins.
lime	4086	#5 4230-47 Open 1 hr. Gas to surf. 2 mins. Gauged
limelshale	4197	2,830 M - 4 mins.
conglomerate	4247	3,020 M - 5 "
lime, shale	4300	3,120 M - 6 "
lime	4315	3,165 M - 15 "
Viola	4378	Stabilized @ 3,165,000 CFG. Rec. 1' muddy wtr, IF
lime, shale	4422	575#, FF 575#, BHP 1350#/30 mins.
shale	4459	Schlumberber Ran.
lime, chert	4481	
arbuckle	4505	
Total Depth		

Tops:
 Heebner 3626
 Toronto 3646
 Douglas 3664
 Brown lime 3766
 Lansing-Kansas City 3775
 Base Kansas City 4036
 Congl. shale 4160
 Congl. chert (Miss.?) 4198
 Kinderhook 4230
 Viola 4289
 Simpson 4413
 Arbuckle 4458

All measurements from rotary bushing.

Drill Stem Tests:

#1 3896-3915 Open 1 hr. Rec. 2980' gas,
 20' oil & gas cut mud. 60' heavily
 O & GCM & 60' very heavily O & GCM.
 IF 50#, FF 80#, BHP 1135#/20 mins.
 #2 3943-71 Open 1/2 hr. Rec. 20' mud.
 IF 0#, FF 0#, BHP 1330#/30 mins.
 #3 4160-90 Open 1/2 hr. Rec. 10' mud.
 IF 0#, FF 0#, BHP 0#/30 mins.
 #4 4190-4225 Open 1 3/4 hrs. Gas
 to surface 2 mins.
 Gauged: 2,630 M - 4 mins.
 3,590 M - 6 "
 3,780 M - 11 "
 3,690 M - 20 "
 3,020 M - 30 "
 2,530 M - 40 "
 2,190 M - 45 "
 2000 M - 59 "
 1,860 M - 55 "
 1,790 M - 60 "
 1,630 M - 65 "
 1,450 M - 70 "