

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- SKELLY OIL CO.
Farm- J.E. Seibert No. 1

SEC. 30 T. 24 R. 15W
SE SF NE
330' EL - 330' SL NE

Total Depth. 4400'
Comm. 11-11-56 Comp. 11-27-56

County Stafford
 KANSAS

Shot or Treated.
Contractor. Claude Wentworth Drlg. Co., Inc.
Issued. 1-26-57



CASING:
8 5/8" 1029' LI 1022' w/500 sx cem.
5 1/2" 4399' LI 967' w/150 sx cem.

Elevation. 2045' DF

Production. Dry

Figures Indicate Bottom of Formations

shale-sand	750	DST # 4 - packer set @ 4334',
red bed-sand	1019	used 66' anchor, open 1 hr.,
anhydrite	1034	weak blow for 55 min., rec.
Reamed 9" hole to 12 1/4"		35' drilling mud, IFP-28#,
red bed-shale	1675	FFP-40#, BHP-68# in 20 min.
shale-shells	1690	
salt-shale	1840	ACID TREATMENT:
shale-shells	2370	No. 1 - between 4297'-4309'
lime-shale	3625	500 gal. - 12-5-56
lime	3685	No. 2 - between 4266'-4271'
lime-shale	3922	250 gals. 12-13-56
lime	3928	
lime-shale	4264	SAND-OIL-FRAC TREATMENT:
chert	4285	No. 1 - between 4297'-4309'
lime-shale	4300	Used 140 bbls. oil.
sand	4307	No. 2 - between 4266'-4271'
lime-shale	4349	Used 87 bbls. heavy oil
dolomite	4400	Ran Lane-Wells.
Total Depth		

TOPS:

Anhydrite	1013
B/Anhydrite	1034
Wellington	1494
B/Wellington	2078
Near Topeka	3241
Heebner shale	3642
Toronto	3660
Douglas	3679
Brown lime	3780
Lansing	3790
B/Kansas City	4054
Marmaton	4112
Conglomerate	4179
Mississippi lime	4264
Kinderhook shale	4294
Kinderhook sand	4296
Viola lime	4349

DST # 1 - packer set @ 3902',
used 28' anchor, open 1 hr.,
weak blow throughout test,
rec. 122' muddy salt wtr,
IFP-30#, FFP-75#, BHP-1284#
in 20 mins.

DST #2 - packer set @ 4258',
used 27' anchor, open 1 hr.,
strong blow throughout test,
gas to surface in 12 mins.,
gas gauged 88 N.C.F., rec.
110' very slightly gas cut
mud, IFP-45#, FFP-62#, BHP-
1196#, in 20 min.

DST # 3 - packer set @ 4284',
used 46' anchor, open 11 hr.,
weak to fair blow throughout
test, rec. 48' of mud w/few
specks of oil, IFP-45#, FFP-
62#, BHP-107# in 20 min.