


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JOHN LINDAS OIL, INC.
Farm- Seibert No. 1

SEC. 31 T. 24 R. 15W
NE NE SE

Total Depth. 4610
Comm. 8-4-52 Comp. 8-25-52
Shot or Treated.
Contractor. John Lindas Oil, Inc.
Issued. 11-8-52

County Stafford
KANSAS



CASING:

8 5/8" 202' cem. w/150 sx
5 1/2" 4280' cem. w/100 sx

Elevation. 2019 DE

Production. 1,667,000 Gas

Figures Indicate Bottom of Formations.

sand & shale strk	170
shale blue	345
red bed	825
shale & shells	1910
lime & shale	2055
lime & sand	2160
shale & shells	2280
lime & shale	2345
lime	2495
shale & shells	2590
shale & lime shells	2855
shale & shells	3030
shale & lime shells	3100
shale & lime	3450
lime	3635
lime & shale	3680
shale & lime shells	3735
lime	4610
Total Depth	

Tops:	
Heebner	3636
Lansing	3787
Congl.	4178
Viola	4264
Simpson	4440
Arbuckle	4510

Perforate 154/4177-4202

Gauge 1,243,000 gas.

Stratofrac: Gauge
1,667,000 gas