


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY  
Farm - Barstow No. 2

SEC. 35 T. 24 R. 15W  
NE SW SW  
990' N & 990' E of SW corner

Total Depth. 4412'  
Comm. 7-16-47 Comp. 8-11-47  
Shot or Treated.  
Contractor. Corbott & Barbour Drilling Co.  
Issued. 10-25-47

County. Stafford  
KANSAS



Elevation. \_\_\_\_\_

Production. Phy. Pot: 22 BO,  
5% B.S., 24 hrs.

CASING:

10-3/4" 304' Com. w/200 sx  
5-1/2" 4403' Com. w/200 sx

Figures Indicate Bottom of Formations.

surface clay & sand	0-45
sand	170
shells	180
shale & shells	308
red bed	935
anhydrite	950
shale & shells	1045
shale & red bed	1345
salt	1640
shale & shells	1900
limo	2467
shale	2785
shale & limo	2985
limo brkn	3040
limo	3636
limo brkn	3690
limo	3730
shale	3756
limo	4122
conglomerate	4191
limo	4221
lime & chert	4256
limo	4345
sand & shale	4370
shale	4398
limo	4402
4402 RTD = 4405 SLM	
limo	4412
Total Depth	

Tops:

Lansing corr.	3735
Conglomerate corr.	4117
Viola corr.	4197
Simpson corr.	4309
Zrbucklo corr.	4402
Penetration	10

Fill-Up

130' oil in 1 hour 40 min.  
450' oil in 4 1/4 hours.  
560' oil in 5 1/4 hours.  
1000' oil in 11 1/4 hours.  
1270' oil in 18 hours.