


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SKELLY OIL CO.
Farm - B. N. Blount No. 1

SEC. 35 T. 24 R. 15 W
SE 1/4 NW
330' fEL & 330' fSL of NW 1/4

Total Depth. 4412'
Comm. 2-21-47 Comp. 3-13-47
Shot or Treated.
Contractor. Claude Wentworth Co.
Issued. 7-26-47

County. Stafford
KANSAS



CASING:

8 5/8" 972' Cem. w/400 sx.
5 1/2" 4405 SLM Cen. w/150 sx.

Elevation. _____

Production. Pot. 243 BO.

Figures Indicate Bottom of Formations.

surface soil, clay & sand	0-85	Tops:	
sand & clay	175	Anhydrite	961
shale blue & clay	235	Lansing Lime	3758
shale & clay	343	Viola Lime	4209
shale	655	Simpson Shale	4321
red bed & gravel	770	Simpson Sand	4340
red bed, sand & shale	835	Arbuckle lime	4403 SLM
shale & red bed	925		
anhydrite	935	Acidized 3-27-47 w/2000 gals.	
red bed & gyp	961	acid 4405-11'	
anhydrite	972	Acidized 3-28-47 w/500 gals.	
anhydrite	985	acid 4405-11'.	
shale & red bed	1300		
shale & shells	1700		
shale	1825		
lime	1840		
lime & shale	3110		
lime	3145		
lime & shale	3395		
lime	3415		
lime & shale	3535		
lime	3660		
lime & shale	3870		
lime	3890		
lime & shale	4135		
lime, shale & chert	4210		
lime & cherty shale	4235		
lime cherty & shale	4270		
lime & chert	4280		
lime, chert & shale	4300		
shale	4303		
lime	4360		
shale	4370		
shale & sand	4398		
sand gy, chert & sdy shale	4404		
xlyn finely gy & coarsely xlyn dolomite, no sat. sli. por.	4406		
dolomite gy & brwn coarsely xlyn, sli. por. & sat.			
med por. & oil sat.	4412		
SLM Corr. 4412=4411'			
show of free oil on cleaned out to btm.			
dolomite brwn & gy coarsely, xlyn, fair por. & sat.,	4412		
bailed & tested 3 hrs.			
, 2 BO & no wtr per Hr.			
Total Depth	4412		