


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM MANAGEMENT & TRANSIT CORP.
Farm- Satterlee "A" No. 2

SEC. 36 T. 24 R. 15W
CE/2 E/2 NE

Total Depth. 4497'
Comm. 7-4-57 Comp. 7-21-57
Shot or Treated.
Contractor. Transit Corp.
Issued. 9-14-57

County Stafford
KANSAS



Elevation. 2007' RB

Production. SWDW

CASING:

8 5/8" 242'
5 1/2" 4462' cem w/125 sx

Figures indicate Bottom of Formations.

surface sand & soil	85
shale & shells	205
shale	242
shale-sand-red bed	935
anhydrite	1380
shale-shell-salt	1785
lime & shale	1855
shale & lime	2845
lime & shale	3203
lime-chalk & shale	3330
lime	3405
lime & shale	3510
hard lime	3596
lime & shale	3775
lime	4148
shale-chert	4285
chert-lime	4315
chert-shale	4350
lime-shale-chert	4380
lime	4497
Total Depth	

TOPS:

Heebner	3588
Brown Lime	3739
Lansing	3750
Base Kansas City	3996
Mississippi	4150
Kinderhook	4182
Viola	4242
Simpson	4322
Arbuckle	4411

DST #1 4114-4190', open 1 hr., weak blow
for nine min., flush the tool, weak
blow for 4 min., recovered 35' of
mud, BHP 0#.