

KANSAS

State Geological Survey
WICHITA, BRANCHWELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 047 — 20,782
County Number

Operator

F. G. HOLL

Address

6427 East Kellogg Wichita, Kansas 67207

Well No.

2-18

Lease Name

Campbell "B"

Footage Location

440 feet from (N) (S) line

440

feet from (E) (W) line

Principal Contractor

Sterling Drilling Co.

Geologist

W. J. Monk

Spud Date

1-8-81

Date Completed

1-13-81

Total Depth

4415'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser


S. 18 T. 24S R. 16 W

Loc. 440 FWL 440 FNL NW/4

County Edwards

640 Acres

N



Locate well correctly

Elev.: Gr. 2090'

Df. 2096' KB 2099'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE		8 5/8"		250'	60/40 Pozmix	225	3% cc.
PRODUCTION		4 1/2"		4413'	Regular	225	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		4323-27'
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	4312'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gallons 15% MCA, 750 Gallons NE acid.	RECEIVED STATE CORPORATION COMMISSION JAN - 7 1982 CONSERVATION DIVISION Wichita, Kansas
525 barrels gelled salt water with 10,000# 20-40 and 10,000#	
10-20 sand.	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
January 1981		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	28.63 MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
SOLD			4323-27		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

F. G. HOLL		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
No.	Lease Name	GAS	
2-18	CAMPBELL "B"		
S 18 T 24S R 16 W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
DST No. 1 4255-4310' 30-30-60-30 Strong Blow: Gas to surface in 15 mins Rad: 125' drilling mud, gassy IFP 63-63 ISIP 593 IHP 2171 FFP 73-83 FSIP 1133 FHP 2233			HEEBNER 3701 BROWN LIME 3827 LANSING KC 3837 BASE KC 4119 CHEROKEE Sh 4237 CHEROKEE Ss ----- MISSISSIPPI 4280 KINDERHOOK Sh 4309 KINDERHOOK Ss 4323 VIOLA 4389 Elog TD 4417
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Elwyn H. Nagel Signature Elwyn H. Nagel Geologist Title June 25, 1981 Date		