

Computer Inventoried

COPY

F. G. HOLL COMPANY

6427 EAST KELLOGG - P.O. BOX 780167
WICHITA, KS 67278-0167

9-24-17W

(ACO-1 Cont.)

McKINNEY #3-9
NE NW NW, Sec 9-24s-17w
Edwards County, KS
API#: 15-047-21,372

DST #1 (4302-4338) Cherokee Sand

1) SBOB, GTS in 26mins. GA: 21.3 MCFGPD

2) Gas Gauges:

10" = 29.4 MCFGPD
20" = 26.1 "
30" = 26.2 "
40" = 27.1 "
50" = 28.5 "
60" = 28.9 "

Times: 30" 60" 60" 90"

REC: 80' Mud/Tr O

120' OGCM (15%G, 8%O)

200' Total Fluid

IHP: 2132 IFP: 75-88:30" ISIP: 1426:60" BHT: 112F
FHP: 2136 FFP: 109-110:60" FSIP: 1390:90"

DST #2 (4345-4385) Mississippi

1) WB inc to SB in 4mins.

2) WB inc to SB in 10mins.

30" 60" 60" 90"

REC: 20' SOGCM (2%G, 1%O, 4%W)
60' SOGCM (10%G, 3%O, 10%W)
60' O&GCW (8%G, 12%O, 40%W)
60' O&GCMW (6%G, 10%O, 46%W)

200' Total Fluid

IHP: 2131 IFP: 61-69:30" ISIP: 1014:60" BHT: 118F
FHP: 2138 FFP: 104-125:60" FSIP: 1040:90"

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1991

CONSERVATION DIVISION
Wichita, Kansas