

Stafford

KANSAS

SECTION 21 TOWNSHIP 24 RANGE 14W

WELL NO. #1 Suiter "B"

COMPANY Lauck & Sunray-Mid-Continent

NORTH

WEST	0							

EAST

SOUTH

HOT FILE

Stafford KANSAS


SEC.	TWP.	R.
21	24	14 W

WELL NO. # 1 Suiter "B" FARM

COMPANY Lauck & SDX (DEVELOPMENT-OBOG)

CONTRACTOR Lauck
Dillwin (Rattlesnake Field)

330 Ft. from N. Line
Ft. from S. Line
Ft. from E. Line
330 Ft. from W. Line
of NW/4
NW NW NW



	ELEVATION	REPORT
1956	1974' DF	1976' KB
	4300' Arbuckle Test	
4/4	Location	(FR Tkt)
4/8	Spudded 4-7-56	
	Drlg. 215' of 8-5/8" csg w/165 sks.	(Card-Lauck Drlg.)
4/9	Drlg. 975'	(DR#69)
4/9	Drlg. 1535'	(Card-Lauck Drlg.)
4/10	Drlg. 2005'	(DR#70)
4/10	Drlg. 2105'	(Card-Lauck Drlg.)
4/11	Drlg. 2440'	
4/12	Drlg. 2620' 2805'	"
4/13	Drlg. 3215'	"
4/14	Drlg. 3585'	"
4/15	Drlg. 3810'	"
4/16	Drlg. 3875'	
	DST #1, 3786-3814, 1 hr, weak blow, 35' very Sli OCM. BHP 95#.(Card-Lauck)	
4/17	Drlg. 3970'	
4/17	Drlg. 3995'	(Card-Lauck)
4/18	Drlg. 4075'	
4/18	Drlg. 4118'	
	DST #2, 4042-4065, weak blow 30 min, 20' mud. BHP 0#.(Card-Lauck)	

OVER

1956
 4/19 Drlg. 4170' (DR#77)
 4/19 Drlg. 4195' (Card-Lauck Drlg.)
 4/20 Drlg. 4230' (DR#78)
 4/21 Drlg. 4301'
 Top Heebner 3514
 B. Lime 3654', Lansing 3674'
 B. KC 3941', Miss 4038', Viola 4142'
 Simpson 4240', Top Arb. 4298'
 5 $\frac{1}{2}$ " set @ 4299 w/100 sax. (Card-Lauck
 Drlg.)
 4/24 TD 4301' No report.
 4/25 TD 4302'. Cleaned out. (DR#81)
 4/26 TD 4305'. Swabbed @ 240 bbls oil
 Day rate. Open hole 4299-4305'
 Arbuckle Zone. COMPLETE (DR#82)
 4-26 Miss. 4038
 DST 4042-65, op $\frac{1}{2}$ hr. rec. 20' mud, Off
 Viola 4138
 Simp. 4239,
 Arb. 4298
 TD 4301,
 5 $\frac{1}{2}$ " @ 4299 w/100
 CO, DD 4302, VSSO,
 DD 4205,
 FU 1000' fluid,
 S/ 54 bo 1st hr.
 S/ 39 bo, 2nd hrs., 33 bo 3rd hrs
 5-3 DD 4305
 FU 1000' oil,
 S/ 42 boph, 3 hrs.
 5-10 Putting on pump
 5-16 P/ 451 bopd, no wtr.
 Grav. 34
 Tops: Anh. 905', H. 3513', BL. 3656',
 L. 3674', BKC 3943', M. 4038', V. 4138',
 S. Sh. 4239, A. 4298'.
 Log tops: Anh. 913', H. 3513', Tr. 3534',
 Dg. 3551', BL. 3654', L. 3674',
 BKC 3941', M. 4038', V. 4112',
 S. Sh. 4239', S. Sd. 4251-69',
 A. 4299',
 TD 4301' **COMPLETED**

County Stafford Elev. 1974
 Sec. 21 Twp. 21 Rge. 14W
 Company Lauck & Sunray Mid-Continent
 Farm Name Suiter #BII No. 1

TOPS	DEPTH	LOG	DATUM	Loc. in Sec.
	905	913		NW NW NW
	3513	3513		
		3534		
		3551		
	3656	3654		
	3674	3674		
L.				Geol.
N.C.				
B.K.C.	3943	3941		Confr. <u>Lauck</u>
Ce.				
C.				
M.	4038	4038		Pool <u>Dillwin</u>
M.				
K.				
Mz.				
Mo.				
V.	4138	4112		
S. <u>3b</u>	4239	4239		
S. <u>3d</u>		4251-69		
A.	4298	4299		
R.				
PE.				COMPLETE
G.				
TD.	4301			

MAY 16 1956

Date Comm.

Location APR 11 '56 Spd 4-7-56 8 5/8

215/165 Anhy 905

APR 18 '56

HD 3513 BL 3656

LS9 3674 DST 3786-3814 or 1hr.

rec. 35' VSOCM BHP 90/30" BKC

3943 ϕ 39PD APR 25 '56 Miss. 4038

DST 4042-65 ϕ 30" rec. 20' Md

All press 0 Viola 4138 Sp 4239 Ar6

4298 (good sh. oil) RTD 4301 5 1/2 4299

1100 Ruct MAY 2 '56 Co DD 4305
FU 1000' oil no time \$ av.
42 Boph no lw 3 hrs \$ 500
O.B. MAY 2 '56 POP no tst. MAY 16 '56 X
wo st tst. Ph. P. 451 Bopd
no wtu gran 34°