

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk. Bldg., Wichita, Kansas


9-24-27W

Company - TEXAS COMPANY  
 Farm - A. L. Seal No. 1

SEC. 9 T. 24 R. 27 W  
 NWc NW  
 330' FNL 330' FWL NW $\frac{1}{4}$

Total Depth. 5550'  
 Comm. 3-9-45 Comp. 4-5-45  
 Shot or Treated.  
 Contractor. Kiowa Drlg. Co.  
 Issued. 5-26-45

County. Gray KANSAS



CASING:  
 13 3/8" 201' Cem.  
 8 5/8" 2060' Cem.

Elevation. 2658

Production. Dry

Figures Indicate Bottom of Formations.

surface-shale-shells 187  
 shale & shells 400  
 water & sand 460  
 shale & shells 750  
 shale & water sand 975  
 shale & shells 1190  
 red bed & shells 1215  
 red bed & anhydrite 1770  
 anhydrite 1825  
 lime 1850  
 shale & shells 2205  
 lime & brkn anhydrite 2305  
 shale & shells 2450  
 anhydrite & red bed 2585  
 shale & shells 2610  
 lime 2690  
 shale & shells 2755  
 lime & shale 3100  
 lime 3550  
 lime & shale 3610  
 lime 3775  
 lime brkn & shale 3810  
 lime 3858  
 lime & shale 3880  
 lime 4010  
 shale 4015  
 lime 4145  
 lime & chert 4320  
 lime & brkn dolomite 4415  
 lime 4580  
 lime & chert 4625  
 lime 4640  
 lime & chert 4680  
 lime 4690  
 lime 4700  
 shale 4708  
 lime & shale 4740  
 lime 4765  
 lime & chert 4780  
 chert 4783  
 chert & lime 4835  
 lime 5100  
 chert 5140  
 lime & chert 5175

Tops: (continued)  
 Viola 5220  
 Simpson 5391  
 Arbuckle 5402  
 Core #1 4690-4703 - 10' Rec.  
 shale & lime  
 Core #2 5194-5209 - 3 1/2' Rec.  
 lime  
 Core #3 5300-5315 - 4 1/2' Rec.  
 dolomite  
 Core #4 5393-5406 - 5' Rec.  
 dolomite, no show.  
 Core #5 5451-5461 - 5' Rec.  
 dolomite porous

lime 5194  
 lime 5250  
 sand 5272  
 lime 5400  
 lime & shale 5420  
 lime & chert 5451  
 lime 5510  
 lime & chert 5546  
 lime 5580  
 Total Depth.

Tops:  
 Stone Corell 1760  
 Lansing 4008  
 Conglomerate 4747  
 Miss. 4764  
 Kinderhook 5134