

SECTION 3 TOWNSHIP 24 RANGE 11 W

WELL NO. #1 Aitken

COMPANY M. F. Lindeman & Sunray Mid-Continent

NORTH

							0

WEST

EAST

SOUTH

HOT FILE**Stafford****KANSAS**

SEC.	TWP.	R.
3	24	11 W

WELL NO. _____

COMPANY **#1 Aitken** FARM

CONTRACTOR **M. F. Lindeman & SDX (EXPLORATORY-BOG)**


Harms-Burt Drlg. Co.**W. Rattlesnake Field Area**

_____ Ft. from N. Line

_____ Ft. from S. Line

_____ Ft. from E. Line

_____ Ft. from W. Line

**NE NE NE****SDX BH****Lse. (S-12337)****1956**

ELEVATION

1950' KB

REPORT

(WH6-BH2)**2/16****Arbuckle test well @ 1250'**

To be commenced by March 2, 1956

To be completed by April 2, 1956

(See Lse. Pur. Agr. Ltr. 2-15-56)

1/25

Location

(FR.Tkt)

2/2

"

2/8

"

2-16

"

2/24

Moving in rotary tools. (Card-Harms-Burt)

2/25Spud and set 210' of 8-5/8" csg
w/200 sks. (Letter-Harms-Burt)**2/26**

Drlg. below surface.

"

2/27

Drlg. 1020' Anhydrite.

Driller's top 863'.

"

2/28

Drlg. 1950'

"

2/29

Drlg. 2275' lime & shale.

"

3/1

Drlg. 2700' in lime & shale.

"

3/2

Drlg. 3085' lime & shale.

"

3/3

Drlg. 3340' lime & shale.

"

3/5

Drlg. 3670' lime.

Tops: Heebner 3471', Br Lm 3613'

Lansing 3630'

"

1956

3/6

DST 3735-57' open 45 min, rec 30'
mud w/ rainbow show of oil.

Drlg. @ 3757'. (Ltr-Harms-Burt Drlg)

3/7

Drlg. 3890'.

Base of Kansas City 3880'. "

3/8

DST #2, 3950-93, open 1 hr, strong
bow thruout, gas to surface in 3
min, rec 150' GCM. Gauge after
45 min, 1,900 MCFG.

Gauge after 50 min, 1,700 MCFG

Gauge after 1 hour, 1,700 MCFG

SIBHP 20" 1280#. IFP 230#.

FFP 270#.

(Ltr-Harms-Burt Drlg.)

3/9

Drlg. 4064'.

3/20

Drlg. 4135'.

Top Simpson shale 4104'

Top Simpson sand 4125' "

3/12

TD 4207' Plugged & Abandoned-(DR#50)

3/15

Advised Contract Section- D & A

ABANDONED

4/2

Received Radiation Guard Log -
Given to S.A. Shannon- Div. Geolog.

County Stafford Elev. _____
 Sec. 3 Twp. (21) Rge. 14W
 Company M. F. Lindeman & Sunray Mid-
 Farm Name Aitken Continent
 No. 1

TOPS	DEPTH	LOG	DATUM
Anh.			
Tr.			
H.			
Tr.			
Dg.			
Bl.			
L.			
K.C.			
B.K.C.			
Ce.			
C.			
M.			
M.			
K.			
Mz.			
Mq.			
V.			
S.			
S.			
A.			
R.			
Pe.			
G.			
T.D.			

Loc. in Sec. NE NE NE

Arb. test

Geol. _____

Contr. _____

Pool _____

Wildcat

FIRST REPORT

JAN 25 '56

Date Comm. _____

Gulf - DHM

Location

Co.

Sec.

No.

Sec.

T.

R.

County Stafford Elev. _____
 Sec. 3- Twp. 12N Rge. 14W
 Company Harms-Burt & Sunray Mid-Continent
 Farm Name Aitken No. 1

TOPS	DEPTH	LOG	DATUM	Loc. in Sec.
Anh.	863			NE NE NE
Tr.				
H.	3471			
Tr.				
Dg.				
Bl.	3613			
L.	3630		1682	Geol.
K.C.				
B.K.C.	3880		1932	Contr.
Ce. <u>Ca</u>	3966		2018	Harms-Burt
C. <u>Cherty</u>	3983		2035	
M.				Pool
M.				Wildcat
K.				
Mz.				
Me.				
V.	3966		2018	
S. <u>V. ch. l.</u>	4035		2087	
S.	4104		2156	
A. <u>S. sh</u>	4125		2177	
R. <u>Arb</u>	4175		2227	
Pe.				
G.				
TD.	4207			

Date Comm. 2-25-56 MAR 14 1956

8 5/8" @ 210/200 DST 3735-55

open 45 min. rec. 30' mud Off

DST 3950-93 open 1 hr. gas in 3 min.

1,900 mcfg in 50 min. 1,700 mcfg

Rec. 150' gcm 1280/20" DST 4128-42

open 70 min. rec. 200' sw 1278/20"

D & A

ABANDONED