

State Kansas County Reno

Company Messman-Rinehart Oil Co. Well No. 1

Farm Brownlee

Survey


Block No. Sec. 31 Twp. 24 S Range 10 W

Co-Ord. Elev. 1757 KB
1754 DF

SE SE NW

M-R Rig

1752 Gr



25% - Messman-Rinehart Oil C

25% - Chicago Group

50% - A. A. Seeligson, Jr.

ORI - Ernest Shamblin
Box 1018, Bristow, Okla.
4185' Sp. test to be comm.

on or before 8-13-58

NOTE: Show Sketch of Lease and Well Location in Above Space

2310

Ft. from N. Line

Ft. from S. Line

2310

Ft. from W. Line

Ft. from E. Line

Date	Depth	
4-29-58		Location staked - C&P
4-30		M.I.R.T. - Spud -
		8-5/8" @ 242' w/170 sx. cem.,
		3 1/2 gel, 3 c.c., PD @ 1:30 a.m.
		5/1/58
5-2	1150	Drlg.
5-4	2450	Drlg. (#3 @ 1987) (#4 @ 2517)
5-5	2955	Making trip - #5 bit
5-6	3205	Making trip - #6 bit

Date	Depth	
		692255
5-7	3475	Drlg.
	3375	Brown Lime (-1618) level
	3391	w/DeMier well Lansing (-1634) 2' higher
	3486	than DeMier well Drlg. (10-12"/ft. (breaks running 2-3' high)
5-8	3565	Drlg. (#6 @ 3505)
	DST #1 - 3476-3505 - Op 1', cl 15",	
		Rec. 310' gas in pipe, 110'
		very sli O&GCM in dr. collars
		180' mdy wtr., BHP (20'')1045#
		(bldg.)
		FP 60-155#
5-9	3705	Drlg. (#8 @ 3595)
5-10	3772	Miss. (-2015) 9' lower than
		Demier well
	DST #2 - 3766-87 - Op 1 hr., good blow	
		throughout, Rec. 2870' SW,
		BHP 1350#, FP 675-1340#,
	3805	Drlg. (#9 @ 3787)
	3930	Viola (-2173)
5-12	4045	Drlg. (#12 @ 4012)
	4049	Simp: Sh. (-2292)
	4066-71	Simp: Sd. (-2309)
	4072	R.T.D.
		D & A - 5-12-58