

16-24-32W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


(NW NW SW NE per footages, KGS)

Company. STANOLIND OIL & GAS CO.
Farm. Mayo Gas Unit "B" No. 1

SEC. 16 SW. 24 R. 32W
NW NW SE NE
1390' S of NL 2620' W of EL NE,
NW NWT SW NE

County Finney

KANSAS



Total Depth. 2595

Comm. 9-1-55

Comp. 9-16-55

Shot or Treated.

Contractor.

Issued. 11-5-55

CASING:
8 5/8 @ 927' w/ 500 sx cmt.
5 1/2 @ 2592' w/ 800 sx cmt.

Elevation. 2827 DF

Production. 12,237,000 CFGPD

Figures indicate Bottom of Formations.

sand & gravel	66
sand	210
shale & shells	645
shale	882
red bed	1240
anhydrite	1265
shale & shells	2040
shale & lime	2360
lime	2595
Total Depth	

TOPS:

Herington	2500
Krider	2530
Winfield	2562

Ran Schlumberger Electric Logs.

Perf. w/ 6 SPF as follows:

Winfield 2552-56

Krider 2563-72

Herington-Krider 2503-08, 2510-16,
2518-24, 2531-33.

Treated Winfield-Krider w/ 400 gal
kero. spacer, 3000 gal Control-Frac
gelled kero. w/ 6000# sand, 1000 gal
kero. flush w/ 1350 gal wtr.

Treated Herington-Krider w/ 400 gal
kero.; 5000 gal Control-Frac gelled Kero.
w/ 10,000# sand, 1000 kero. flushed
w/ 1500 gal wtr.