

WILDCAT

1-316W

MAP NO.

K-77

SEC.

22-24S-32W

STATE Kansas

COUNTY

Finney

LOC.

C NW NE

OPER. Aikman Bros. - Amarillo, Texas

FT/FR

LINE

WELL #1

FARM Ramirez

AS

2817

FT/FR

LINE

DL WC

ELEV.

2814

GR.

2816

DF

2819

KB

CONT. Strata Drlg.

GEOLOGICAL

Paul Buckthall

INT. 5100' St L Test - Pan American Support

F.R. 12-28-64

SPUD

1-2-65

COMP.

1-28-65


TD. 4920

FM.

St L

PBTD.

D & A



COMP. RECORD

WC-6 mi NE of Cowgill (Morr oil) Pool)

8 5/8" @ 504' w/500 Sx.

Data Inc.

(KB Log Tops:)

Hb 3840 -1021

Lans 3879 -1060

Des M 4414 -1595

Mrw 4696 -1877

St G 4716 -1897

St L 4759 -1940

LTD NA

RTD 4920 -2101

DST #1 (St L) 4790-4866, (Str Pkr) Op

120", 5' Pre-flow fr blo, R 1153' G &

sli OCMSW, ISIP 1282#/30", IFP 44#, FFP

449#, FSIP 1138#/30"

DST #2 (St L) 4766-90, (Str Pkr) Op 1 hr,

5" pre-flow, V wk blo for 1', by-pass tool

18', R 50' MW/NSO, ISIP 1298#/30", IFP

48#, FFP 50#, FSIP 712#/30", RTD 4920,

Ran Logs, D & A 1-18-65 - COMPLETED

2 mi west of City on the way

OKLAHOMA CITY ELECTRIC LOG TOPS

2819 KB

Winfield 2560 (+259)
Heebner 3840 (-1021)
Toronto 3850 (-1031)
Lansing 3879 (-1060)
Marmaton 4408 (-1589)
Morrow 4696 (-1877)
Ste. Gen 4716 (-1897)
St. Louis 4759 (-1940)
TD 4920 D & A