

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


13 - 24 - 34 W

KANSAS-NEBRASKA NAT.GAS CO., INC.
Layman No. 1.

SEC.13 T.24 R.34 W
Gen Sec.

Total Depth. 2733'
Comm. 5-31-42 Comp. 6-20-42
Shot or Treated.
Contractor. Clay Bros.
Issued. 8-29-42

County. Finney



CASING:
10 3/4" 450'7" Cem.
7" 2527' Cem.
5 3/16" liner 218'

Elevation.

Production. 1,900,000 G.

Figures Indicate Bottom of Formations.

sand & gravel	450
clay shale	650
sand & gravel	700
shells	760
shale	845
shale red & blue	1090
red bed & shells	1740
red bed shale	1810
red rock shale, gypsum	1975
red bed & shells	2080
red rock shale & brkn lime	2280
anhydrite, shale, brkn lime	2340
shale, shell, conglomerate	2350
anhydrite & lime	2410
shale, brkn lime	2523
shale	2527
lime	2547
lime brkn	2560
lime gy	2575
lime	2585
lime brkn	2620
lime gy	2660
lime	2665
shale pink	2670
lime brkn gy	2700
lime gy	2715
lime	2733
Total Depth.	

sh gas 2560-62
increase at 2622

48 hr shut-in R.P. 424#
15 min. blow down
I.P. 1.9 million cu ft