

WICHITA BRANCH

Kans. Geo. Survey request
samples on this well.

KANSAS DRILLERS LOG

API No. 15 — 055 — 20,296
County Number

Operator

Champlin Petroleum Company

Address

2601 N.W. Express., Suite 800E, Okla. City, Okla. 73112

Well No.

#2

Lease Name

Jones Gas Unit

Footage Location

1300 feet from (N) ~~1/2~~ line 2640 feet from ~~1/2~~ (W) line

Principal Contractor

Service Drlg. Co.

Geologist

D. Elich

Spud Date

7-17-78

Total Depth

3110

P.B.T.D.

3065

Date Completed

9-6-78


Oil Purchaser

Kansas-Nebraska Nat Gas Co.

S. 2 T. 24 R. 34 ~~W~~

Loc. C N2

County Finney

640 Acres
N

Locate well correctly

Elev.: Gr. 2902

DF KB 2911

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	20#	735	35-65 poz Class H	200 150	18% gel fol 12% CaCl
Production	7-7/8	5-1/2	14#	3099	Litewate 50-50 poz	500 100	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.48 jet	2726-36, 2749-66
TUBING RECORD			2	.48 jet	2776-88, 2796-2800
Size	Setting depth	Packer set at			
2-3/8	2908				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
120,000 gal water, 120,000# 20-40 sand @ 130 BPM	2726-2800
250 gal 15% HCL, 6000 gals 7-1/2% HCL loaded in csg	2726-2800

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
S.I. Waiting on connection	pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbls.	est. 1404 MCF	est 8 bbls.		
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Vented during completion (S.I. waiting on connection)			2726-2800		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Champlin Petroleum Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

gas

Well No.

2

Lease Name

Jones Gas Unit

S 2 T 24 R 34 ^K_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Red bed, sand, shale

0

945

Dual Induction

3111

Sand, shale

945

2615

focused log

Shale, lime

2615

2812

Nuclear Log

3067

Lime

2812

3110

TD

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

District Clerk

Title

11-22-78

Date

2-24-34w

Champlin Petroleum Company

Jones Gas Unit No. 2
Finney County, Kansas

COMMENCED OPERATIONS: 7-18-78
COMPLETED OPERATIONS: 7-23-78

DRILLERS LOG

7-18-78	0 - 955	Redbed, Sand, Shale.
7-19-78	945 - 2010	Sand, Shale.
7-20-78	2010 - 2615	Sand, Shale.
7-21-78	2615 - 2812	Shale, Lime.
7-22-78	2812 - 3100	Lime.
7-23-78	3100 - 3110	Lime.

CASING RECORD

7-18-78	Ran 18 joints 8 5/8" new 20# casing. Set at 735'. Cemented with 200 sacks 35/65 with 18% gel fol. with 150 sacks Glass II with 12% C.C.
7-24-78	Ran 88 joints 3 1/2" 14# casing. Set at 3099'. Cemented with 500 sacks LNT follow with 100 sacks 50/50 Poz, 18% salt.

State Geological Survey
Champlin *WICHITA*

November 22, 1978

15-055-20296

2-24-34W

Kansas Geological Survey
4150 Monroe
Wichita, Kansas 67209

Gentlemen:

Attached is Gamma Ray-Nuclear Log and Induction Electric Log on
Champlin's Jones Gas Unit No. 2 located C N/2 Section 2-T24S-R34W, Finney
County, Kansas, in accordance with Corporation Commission Rule #82-2-125.

Yours very truly,

CHAMPLIN PETROLEUM COMPANY



H. E. Melvin, District Clerk

HEM:jm

Champlin Petroleum Company
Oil Center East
2601 Northwest Expressway
Suite 800E
Oklahoma City, Oklahoma 73112
405/840-5521