

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

Wichita, Kansas

7-24-34W


Company - STANOLIND OIL & GAS CO.  
Farm - Crawford Gas Unit No. 1

SEC. 7 T. 24 R. 34W  
SE NW SE

Total Depth. 2650 P.B. 2610  
Comm. 8-21-49 Comp. 10-15-49  
Shot or Treated.  
Contractor.  
Issued. 12-24-49

County. Finney

KANSAS



CASING:  
10" set @ 815' w/500 sx.  
7" set @ 2624' w/100 sx.

Elevation. 2928 ft.  
2923 act.

Production. 2,929,000CFG

Figures Indicate Bottom of Formations.

|                    |      |
|--------------------|------|
| Sand & clay        | 570  |
| Sandy lime         | 645  |
| Shale              | 670  |
| Shale, lime shells | 750  |
| Shale              | 790  |
| Red bed            | 1275 |
| Red rock           | 1310 |
| Gray lime, shale   | 1405 |
| Red sand           | 1580 |
| Red rock           | 1870 |
| Lime               | 1985 |
| Lime, shale        | 2055 |
| Lime, gyp          | 2110 |
| Lime, shale, gyp   | 2230 |
| Lime               | 2400 |
| Lime, shale        | 2530 |
| Lime               | 2650 |

Total Depth P.B. 2610

Halliburton temperature survey  
Ran Schlumberger

Acid engineers acidized all zones individually w/1000  
gals. 15% each. Reacidized all zones w/26,000 gals.