

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

Operator: License # 5952

Name: BP AMERICA PRODUCTION COMPANY

Address P. O. BOX 3092, WL1-RM 3.201

City/State/Zip HOUSTON, TX 77253-3092

Purchaser: WGP-KHC, L.L.C.

Operator Contact Person: SUE SELLERS

Phone (281) 366-2052

Contractor: Name: CHEYENNE DRILLING

License: 5382

Vellsite Geologist: _____

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover
☐ Oil ☐ SWD ☐ SLOW ☐ Temp. Abd.
☒ Gas ☐ ENHR ☐ SIGW
☐ Dry ☐ Other (Core, WSW, Expl., Cathodic, etc.)

Workover/Reentry: Old Well Info as follows:

Operator: _____

Well Name: _____

Comp. Date _____ Old Total Depth _____

Deepening ☐ Re-perf. ☐ Conv. to Inj/SWD

Plug Back ☐ PBTD

Commingled ☐ Docket No. _____

Dual Completion ☐ Docket No. _____

Other (SWD or Inj?) ☐ Docket No. _____

2/25/03 2/27/03 4/11/03

Spud Date Date Reached TD Completion Date

API NO. 15- 093-21726-0000

County KEARNY

SE SE SE Sec. 14 Twp. 24S Rge. 35W X E W

330' S Feet from SW (circle one) Line of Section

330' E Feet from EW (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
NE SE NW or SW (circle one)

Lease Name MARTIN A Well # 3

Producing Formation COUNCIL GROVE

Elevation: Ground 2936' KB 2943'

Total Depth 2907' PBTD 2907'

Amount of Surface Pipe Set and Cemented at 968' Feet

Multiple Stage Cementing Collar Used? ☐ Yes ☒ No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan ALT 1 gyl 7/22/03
(Data must be collected from the Reserve Pit)

Chloride content 12,000 ppm Fluid volume 750 bbls

Dewatering method used DRIED AND FILLED

Location of fluid disposal if hauled offsite: _____

Operator Name K & L TANK

Lease Name MORRIS B1 SWD License No. 8757

_____ Quarter Sec. 19 Twp. 24 S Rge. 31 E/W

County FINNEY Docket No. 16-812 (96-930C)

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Sue Sellers

Title STAFF ASSISTANT Date 05-07-03

Subscribed and sworn to before me this 7TH day of MAY

20 03

Notary Public Ann Thompson

Date Commission Expires 4-30-04



K.C.C. OFFICE USE ONLY

F ☒ Letter of Confidentiality Attached

C ☒ Wireline Log Received

C ☐ Drillers Timelog Received

Distribution

☐ KCC ☐ SWD/Rep ☐ NGPA

☐ KGS ☐ Plug ☐ Other

(Specify)

Operator Name BP AMERICA PRODUCTION COMPANY Lease Name MARTIN A Well # 3
Sec. 14 Twp. 24S Rge. 35W ☐ East ☒ West County KEARNY

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken (Attach Additional Sheets.)	☐ Yes ☒ No	☒ Log Formation (Top), Depth and Datums ☐ Sample NameTopDatum CHASE 2406'KB COUNCIL GROVE 2694'KB
Samples Sent to Geological Survey	☐ Yes ☒ No	
Cores Taken	☐ Yes ☒ No	
Electric Log Run (Submit Copy.)	☒ Yes ☐ No	
List All E.Logs Run: COMPENSATED SPECTRAL NATURAL GAMMA		

CASING RECORD ☒ New ☐ Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
SURFACE	12 1/4"	8 5/8"	24#	968'	PLITE3%/'C'	295 SXS	2%CC:1/4#FLOC
					PLITE3%/'C'	125 SXS	2%CC:1/4#FLOC
PRODUCTION	7 7/8"	4 1/2"	10.5#	2,907'	PLITE3%/'C'	555 SXS	1/4# FLOCELE

ADDITIONAL CEMENTING/SQUEEZE RECORD				
Purpose	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
☐ Perforate				
☐ Protect Casing				
☐ Plug Back TD				
☐ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	2710-2730'	FRAC-W/48,900# 16/30 BRADY SAND	2710-2730
		& 745,000' 80Q N2 FOAM	
		ACID-W/500 GALS OF 15% HCL	2710-2730

TUBING RECORD		Size 2 3/8"	Set At 2745'	Packer At NA	Liner Run ☐ Yes ☒ No
Date of First, Resumed Production, SWD or Inj. 4/11/03			Producing Method ☐ Flowing ☒ Pumping ☐ Gas Lift ☐ Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
0		112	0		

Disposition of Gas: METHOD OF COMPLETION Production Interval
☐ Vented ☒ Sold ☐ Used on Lease ☐ Open Hole ☒ Perforation ☐ Dually Comp. ☐ Commingled
(If vented, submit ACO-18.) ☐ Other (Specify)