

KANSAS DRILLERS LOG

API No. 15 — 093 — 20,465
 County Number

Operator Champlin Petroleum Co. MAY 16 2002

Address 6051 North Brookline, Suite 116 Okla City, Okla 73112 KCC WICHITA

Well No. #2 Lease Name Orlie White

Footage Location 1980 feet from (N) line 1980 feet from (E) (W) line

Principal Contractor Service Drilling Company Geologist D. Elich


Spud Date 11-9-77 Total Depth 3013 P.B.T.D. 2965

Date Completed 12-7-77 Oil Purchaser Gas- Colorado Interstate

S. 7 T. 24 R. 36 ⁴/_W

Loc. C SE NW

County Kearny



Elev.: Gr. 3094

DF KB 3102

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Csg	12-1/4	8-5/8	23	771	50-50 Poz Class H	250 150	2% CaCl 2% CaCl
Production Csg	7-7/8"	5-1/2"	14	3013	Lite wate 50-50 poz	500 100	12-1/2# gilsonit 18% salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	Jet	2796-2912

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	2916	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2500 gals 15% HCL acid	2796-2912
Frac w/120,000 gals water, 120,000# 10-20 sand	2796-2912

INITIAL PRODUCTION

Date of first production <u>12-7-77</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Flowing</u>		
RATE OF PRODUCTION PER 24 HOURS	Oil <u>None</u> bbls.	Gas <u>2992 est</u> MCF	Water <u>25</u> bbls.
Disposition of gas (vented, used on lease or sold) <u>Vent - now S.I. waiting on gas connection</u>		Gas-oil ratio <u>None</u> CFPB	
Producing interval (s) <u>2796-2912</u>			

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Dr Logs will be on open file in the Oil and Gas Division, e Geological Survey of Kansas, Lawrence, Kansas 66044.