

90063



1-106W

MAP NO. OWWO

SEC. 31-24S-36W

STATE Kansas COUNTY Kearny

LOC. C NE NE

OPER. W. B. Osborne - San Antonio, Texas

FT/FR _____ LINE _____

WELL #1 FARM Moser

FT/FR _____ LINE _____

WC


ELEV. 3100 0 GR. 3107 0 DF 3110 0 KS

CONT. _____ GEOL. _____

INT. _____

F.R. 8-19-64 SPUD 4-12-63 (old) COMP. 1-14-65

TD. 5087 FM. Sperg PBD. 5000



COMP. RECORD

Miss 4946-4966 48 5000A & Frac

State Pot: P 10 BOPD / tr W (Gr 27.2 deg)

WC-Moser Disc. - 8-5/8" @1883' w/1200 Sx., 5 1/2" @5087' w/225 Sx.

Data Inc.

(KB Log Tops:(Old) OLD INFO: (Was CSO)

Winf	2470 / 640	DST #1 (CG) 2830-57, Op 1 hr, R 70' MW,
CG	2688 / 422	No ISIP, IFP 22#, FFP 44#, FSIP 468#/30",
Hb	3696 - 586	DST #2 (Lan) 3685-3725, Op 1 hr, R 310' WM,
Tor	3708 - 598	No ISIP, IFP 53#, FFP 160#, FSIP 936#/30"
Lans	3736 - 626	DST #3 (Lans) 3735-56, Op 1 hr, R 1230' M
Marm	4274 -1162	sulf wtr, IFP 80#, FFP 402#, FSIP 936#/30"
Morr fm	4710 -1600	DST #4 (Marm) 4291-4303, Op 40", R 1' oil
Morr sd	4736 -1626	4' OCM, ISIP NA, IFP 7#, FFP 17#, FSIP
St L	4822 -1712	962#/15"

"B"	4940 -1830	DST #5 (Marm) 4295-4323, Op 1 hr, R 10' O
"C"	5020 -1910	&GCM, 230' OCM, ISIP NA, IFP 44#, FFP 131#
Sperg	5020 -1970	FSIP 1114#/15",
LTD	NA	DST #6 (Morr) 4737-50, Op 1 hr, R 2705' SW,
RTD	5087 -1977	ISIP NA, IFP 1084#, FFP 1301#, FSIP 1301# / 30"

DST #7 (St L) 5020-30, Op 1 hr, R 15' M, No ISIP, IFP 22#, FFP 22#, FSIP 891#/30", RTD 5087 (Sperg) Sj Log,

WLT#1 (Marm) 4328-30 1/2, Op 2 hts, R 25,400 cc filt W, ISIP 1230#/10" IFP NA, FFP NA, FSIP 1230#/10"

WLT #2 (Lans) 3832 1/2, Op 2 hrs, R 2200 cc filt W, ISIP 1050#/40", No FP's, FSIP 1050#/40", D & A - COMPLETED 5-3-63

NEW INFO:(8-19-64) CO 5087' OTD, 5 1/2" @5087' w/225 Sx., WOCT, MICT 32/5034-42, (St L "C") \$ dry, Pf 32/5022-30 (St L "C") \$ dry, 1000 MCA, \$ 1d, No shows, / 2 GSWPH, NT, PB, 5000 PBD, Pf 16/4962-66, 32/4946-54 (St L "B") FU 60' oil, NT, \$ 1/2 BOPH, NW/NT, 1000A, \$ 1d, \$ 2 BOPH, NW/NT, Co 5000' oil, NW/NT, \$ 2-1/3 BOPH - NW/NT, \$ 90 BO/NW/20 hrs, Frac (7500 Gell oil x 3750# sd), \$ Pt 1d, P 40 to 45 BOPD / tr W, State Pot: P 10 BOPD / tr W, Gr 27/2 Miss 4946-54, 4962-54, 4962-66, (Moser Discovery) - COMPLETED 12-30-64

Was: 31-23S-36W, Is: 31-24S-36W - REPLACEMENT COMPLETION 1-11-65