

90148 5

Field Hayton

State Kansas

County Kearney

Company Stanolind Oil & Gas

Farm Forst

Well No. 1

Sec. 3 Twp. 24S Blk. 24S

Range 37W Survey

fr N fr E fr S fr W

of SW SW NE

Contractor Noble Drlg.

Remarks

Comm. 10-10-55

Comp. 11/16/55

Elev. 3267 DF

T. D. 2705

P. B.

Pay 2527-32 - 2540-54 2575-90 - 2597-2602

2624-28 - 2642-51 2672-76

I. P. 11,154 MCF R. P.

Casing Record: 13 3/8 7

20 10 3/4 5 1/2 2703/100

16 8 5/8 728/500

10-19-55 RTD 2705, ran log Tops Her-Kri 2518  
Winf 2575  
Tow 2737  
Ft. Riley 2672

~~OCT 26 1955 WOCT~~

*ran 5 1/2 @ 2703/100*

NOV 2 1955

MICT CO 2698  
~~pup to pf.~~

NOV 9 1955

pf 16/2672-76 32/2680-88  
flow/400 + 3000 gal kero + 6000 sd  
g 2,468 mcf PD + 7 gal kero ph  
set plug 2655 - 16/2642-46  
12/2648-51 16/2624-28 - flow/400  
+ 3000 gal kero + 6000 # sd g 3,489 mcf  
PD + 90g kero ph. later gings test  
g 3,232 mcf PD + 35g kero ph.  
set plug 2606 20/2575-80 20/2585  
90 20/2597-2602 flow/400 kero  
+ 4000 gal kero + 8000 sd g 3,489 mcf.  
P.D. + 96g kero ph - 3,605 mcf PD  
+ 35g kero ph - plug at 2558

*set plug*

20/2527-32 56/2540-5# flax/400 Kero  
+ 400 gel gel Kero + 6000 sd. Co to 2558  
sent. + g 5,600 muf PD + 150 g Kero PH  
4,505 muf PD + 20g Kero ph.

blowing

Ø all plays -

NOV 16 1955

20" open 11, 154 muf  
SIP 252 #

Ø