


90073

2-204W MAP NO. 78 SEC. 16-24S-37W
 STATE Kans COUNTY Kearny LOC. C NW SE
 OPER. Pan American Pet. Corp. FT/FR _____ LINE _____
 WELL 2 FARM Vernon G. Kropp FT/FR _____ LINE _____
 L Geol-Wc-Hugoton Field ELEV. 3266 GR. 3273 DF 3275 KB
 CONT. Big Chief Drlg. Co. GEOL. _____
 CO. 5200' Gas Test
 INT. _____
 F.R. 1-29-63 SPUD 1-28-63 COMP. 2-26-63
 TD. 5280 FM. Ste Gen PBTD. _____
 COMP. 8 5/8" @2105/200 sx. D&A



(KB Spl)

(KB Log)

Data Inc.

Mo	3882	Chase	2589	+ 686
Morr	4820	CG	2858	+ 417
RTD	5280	Penn	3314	- 39
		Mo	3933	- 658
Ran Log, 5200', DD to RTD		Des M	4488	-1213
5280,		Morr	4922	-1647
WLT #1 (Mo) 4244, Op 1 hr, R		Ste Gen	5213	-1938
20,600 cc wtr (less than		LTD	5280	-2005
5% form wtr) ISIP 1350#/45"				
FSIP 1330#/60"				

WLT #2 (Penn) 3720-22½, Op 1 hr, R 9100' cc Wtr, ISIP 930#/
 8", SP Less than 50#, FSIP 930#/6" (No Geologist - Gas
 Dector on Location) D&A COMPLETED (2-17-63)

LIBERAL ELECTRIC LOG TOPS

3275 KB

Winfield 2650 (+625)
Council Grove 2848 (+427)
Heebner 3878 (-603)
Toronto 3894 (-619)
Lansing 3934 (-659) WLT XW
Marmaton 4503 (-1228)
Morrow 4948 (-1673)
"S-3" 5060 (-1785) 18/44; NT
Ste. Gen 5202 (-1927)
TD 5279 D & A