


Company- STANOLIND OIL & GAS CO.
Farm- Martin Gas Unit "C" No. 1

1-24-38W
SEC. 1 T. 24 R. 38W
C NW/4
1320' S of NL, 1320' E of WL

Total Depth. 2751' PB 2711'
Comm. 11-18-54 Comp. 12-26-54
Shot or Treated.
Contractor.
Issued. 1-29-55

County Kearny
KANSAS



CASING:
8 5/8" 815' cem w/400 sx
5 1/2" 2720' cem w/950 sx

Elevation. 3316' DF

Production. 20-in. Open Flow
4,630,000 MCF Gas

Figures indicate Bottom of Formations.

sand - clay 40
sand - shale 615
shale 775
red bed 970
shale-sand-shells 1290
anhydrite 1310
shale-anhydrite 1725
shale 2040
shale-lime 2751
Total Depth PBD 2711'

Tops:
Herington Krider 2577
Winfield 2631
Towanda 2692
Ft. Riley 2720

Schlumberger ran Gamma Ray & Micro Log.
Ran 1 1/2" Tubing set at 2707'

Halliburton acidized as follows:

Ft. Riley w/250 gal 7 1/2% acid w/5 gal
Petrowet, 2500 gal 10% w/5000# sand,
1250 gal 7 1/2% acid w/8 gal Petrowet,
flushed w/2750 gal water.

Winfield and Towanda w/250 gal 7 1/2% acid
w/5 gal Petrowet, 1500 gal gel 10% w/3000#
sand, 750 gal 7 1/2% acid w/5 gal Petrowet,
flushed w/2500 gal water.

Winfield and Herington Krider w/7000
gal gel 10% w/14,000# sand, 4000 gal 7 1/2%
acid w/34 gal Petrowet, flushed w/2500
gal water.

Perforating Guns Atlas Corp. perforated
w/6 shots per foot as follows:

Towanda - 2698-2703'.
Winfield - 2690-92', 2678-82', 2631-43',
2650-56'.
Herington Krider - 2580-96', 2600-02',
2607,09', 2611-17'.

20-in. Open Flow 4,630,000 MCF, SIP 360#