

Mid-Continent Petroleum Corporation
 Clare A. Stewart Well #1
 NW NW SE Sec. 29-24-38W
 Kearney County, Kansas
 Commenced: 4/16/48
 Completed: 5/20/48
 Initial Production: 5,600,000 cu. ft.

Casing: 8 5/8" 681' W/350 Sbx.
 5 1/2" 2598' W/375 Sbx.

Formation	Top	Bottom
Surface clay & sand	0	70
Water sand	70	106
Sand & clay	106	290
Water gravel	290	300
Sand & clay	300	600
Blue shale	600	650
Red bed	650	700
Red bed & shale	700	1572
Salt & shale	1572	1878
Shale & sand	1878	2154
Shale & Anhydrite	2154	2434
Herington dolomite	2434	2444
Shale	2444	2447
Krider dolomite	2447	2468
Shale	2468	2493
Winfield dolomite	2493	2514
Shale	2514	2557
Towanda dolomite	2557	2568
Shale	2568	2593
Dolomite	2593	2598
Shale	2598	2602
Fort Riley dolomite	2602	2616
Fort Riley	2616	2624 T.D.