

KANSAS

Kearny



Sec. 29 Twp. 24 R. 38W

Well No. #1 C. Stewart Farm

Mid-Continent Pet.....75% Company


Hugoton GJ.Smith.....25% NORTH

100 Ft. from N. Line

 Ft. from S. Line

 Ft. from E. Line

100 Ft. from W. Line



NW SE

Noble Drlg. Contractor

1948

Elev. 3241'

REPORT

2675' Test

- 4/14 Location
- 4/16 Moving in tools. (P.R)
- 4/19 Spud 4-16-48
- 8-5/8" csg. set 682' w/350 sacks. "
- 4/20 Drlg. 1250' "
- 4/21 Drlg. 2310'
- 4/22 Top Harrington 2438'
- 4/23 5 1/2 casing set 2598' w/375 sacks.
- Schl. tops:
- Harrington 2434'-44'
- Crider 2447'-58'
- Windfield 2493'-2514'
- Towanda 2557'-71'
- Sample top Ft. Riley 2603'
- WOC "
- 4/27 T.D. 2605'
- 5" set 2598'
- Drilling out cement. (Tel)
- 4/28 Acid. w/500 gal.
- Making 3 gal. acid water per hr.
- Slight increase in gas.
- Will drill deeper & acidize. (P.R)
- 4/29 Acid. w/3000 gal. Now making
- 496,000 cu.ft. gas per day in
- Ft. Riley. Will perforate & acidize
- other formations. T.D. 2624'. (P.R)

OVER

1948

- 4/30 Perf. 72 shots 2493'-2514'
Acidized w/500 gal. & 3000 gal
Making 1,400,000 cu.ft. gas per day.
Will drill out plug today, set another
plug, perf., & acidize in another zone.
T.D. 2624' (P.R)
- 5/3 Set plug 2477'
Perf. 93 shots 2434'-44'
2447'-68'
(Harrington & Crider zones)
Acidized again w/7500 gals.
Making total of 18,000 gal.
Will test. (P.R)
- 5/4 Testing "
- 5/5 Testing. Will report on Wednesdays. "
93 shots 2434-67
18,000 acid
1½ M Gas
- 5/12 Testing 2624' "
- 5/12 3,800,000 gas.
- 5/19 Taking 72 hr. gauge. "
- 5/20 Comp. 5,600,000 cu.ft. gas per day.
420# SI Pressure. 20 min. blow down.
T.D. 2624' "
- 5/26 5½" @ 2598'
Perf
Acid 18,000
Gas 5,600,000
R. Pr. 420#
TD 2624'

COMPLETED

Map No. _____ Sec. 29 Twp. 24 R. 38W

Well No. 1 C. Stewart

Mid-Continent Petroleum Company

COMPLETE

Contractor

NW SE

E 13241
SECTION PLAT

100 Ft. from N. Line

_____ Ft. from S. Line

_____ Ft. from E. Line

100 Ft. from W. Line

		0	

Kearny County

Location _____

Rig up _____

Drilling and Remarks:

5 1/2 C2578

Prof.

18000 acs

5,600,000 Gas

420" R/P

RECORD

Cased _____ in., _____ ft.

Sand _____

Gas _____

Oil _____

Total Depth 2624

PRODUCTION

1st 24 hrs. Nat. _____

1st 24 hrs. after shot _____

Gas _____ Cu. Ft.

Dry Hole _____

Abandoned _____

Date

MAY 26 1948

19

S. J. LEWIS

Scout

Map No. _____ Sec. 29 Twp. 24 R. 38W

Well No. 1 C. Stewart

Mid-Continent Pet. Company

FIRST REPORT Contractor

NW SE

SECTION PLAT

100 Ft. from N. Line

_____ Ft. from S. Line

_____ Ft. from E. Line

100 Ft. from W. Line

		0	

Kearny County

Location X

Rig up _____

Drilling and Remarks:

RECORD

Cased _____ in., _____ ft.

Sand _____

Gas _____

Oil _____

Total Depth _____

PRODUCTION

1st 24 hrs. Nat. _____

1st 24 hrs. after shot _____

Gas _____ Cu. Ft.

Dry Hole _____

Abandoned _____

Date

APR 14 1948 19 S. J. LEWIS Scout