

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. CNW NW Sec. 2 T. 24 R. 4W.
660' NL 660' WL. NW 1/4

Casing Record. County. Reno.
10" Farm. P. D. Frantz, 'A' No. 1
20" 8 1/2" 3286 Company. Gled Oil Co., Skelly - Shell.
15 1/2" 248 35/8" Contr.
12 3/8" 53/16" Comm. 6-17-32 Comp. 9-1-32
Total Depth. 3495 Shot Quarts Between.
Correspondence Regarding This Well Should Be Referred To.



Elevation. 1468

Figures Indicate Bottom of Formations. Initial Production.
Date Issued. 9-10-32 Flow 120 oil and 65 wtr
in 24 hours, thru 3"
tubing Oil 25° gravity.

Formation	Depth.
surface sand and red rock	251
shale	525
shale and shells	1600
shale and lime	1750
shale and shells	1895
shale and lime	1985
lime	2045
sand and lime	2055
broken shale and lime	2090
broken lime	2330
lime	2410
broken shale and lime	2455
sand	2515
lime	2655
broken lime	2802
lime	3100
broken lime and shale	3175
lime	3230
variegated shale	3280
Chat top chat 3280	3296
3296 equal 3293 S.L.C.	
chat	3320
Gauged 6,016,000 gas. 1105 # R.P. in 1 hr.	
chat	3373
chat	3381
Unloaded hole at 1 P.M. 7-16-32. flow estimated 15 bbls., Per hr. two thirds water and one third oil At 7 A.M. on 17th flowing 5 bbls hour, one half oil and one half water. well killed and hole loaded at 3381.	
chat	3420
lime	3442
lime and chat	3465
lime	3495.
hole unloaded at 3495. Gauged 9,000,000 gas Est. 10 bbls fluid Flowed 210 bbls fluid in 6 hr 20 min. 7-28-32. (PHr 31% BS & W. 115 bbls cut oil and 95 bbls water well shut in 36 hrs when test was taken.	
T.D.	3495

3280
1468

1812