

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.  
Mary Collins No. 2.

SEC 3 T. 24 R. 4W.  
SE NW SW  
990' fr N.L. 330' fr E.L.  
W $\frac{1}{2}$  SW $\frac{1}{4}$

Total Depth. 3606  
Comm. 6-22-36 Comp. 7-23-36  
Shot or Treated.  
Contractor.  
Issued. 10-3-36

County. Reno.



CASING.

15 $\frac{1}{2}$ " 359' 85/8" 3599'

Elevation.

Production. Pot. 678 B.  
20BW.

Figures Indicate Bottom of Formations.

sand	170	shale and shell	3565
shale	360	shale	3596
shale and lime shells	845	corod 3591-96 all shale	
lime	870	corod 3596-3601 lime Hunton	
shale and lime shells	1015	lime	3601
lime	1035	lime hard show oil	3604
shale and lime shells	1085	lime sdy	3606
broken lime	1160	Total Depth.	
shale	1170	Top Hunton 3599 $\frac{1}{2}$	
shale and shell	1375		
shale	1489		
shale and shell	1680		
shale	1893		
shale and lime shells	1980		
broken lime	2051		
lime	2104		
shale and lime shells	2230		
shale	2254		
shale and lime shells	2345		
lime	2365		
shale and lime shell	2382		
broken lime and shale	2424		
broken lime	2463		
shale and lime shells	2547		
shale and lime	2607		
lime	2698		
lime K.C.	2879		
lime hard	2897		
lime	2952		
shale	2962		
shale and lime shells	3005		
shale and lime	3086		
shale sticky	3111		
shale	3192		
shale and lime shells	3232		
shale and lime	3268		
shale	3269		
chat	3451		
lime	3505		
shale	3535		

Handwritten calculation:  
3269  
1470  
-----  
1799

Sinclair Prairie #2 Collins  
Sec. 3-24-4W SE NW SW  
Comm. 12-26-41 Comp. 1-23-42  
Pot. 54 BO  
Last prod. 3 BO, 30 BW; Set  
Lane-Wells drillable plug  
at 3420' top of cement  
3360; Perf. the 85/8" in  
chat 12-29-41; 3320-40  
20 shots, slight sh gas, no  
oil; 3340-46 42 shots,  
showed 10' oil in bailer in  
2 hrs; 3285-92 80 shots,  
for inc. in gas & fillup  
450' oil in 16 hrs, w/  
good sh gas; Tested for 10  
days, well good for 30 to  
35 BO, 10 BW daily