

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.

Almeda M. Hefling (formerly OB Showalter) No. 3

SEC. 8 T. 24 R. 4W.

CEL SE

330' fr E. 1320' fr S. lines.

Total Depth. 3374

Comm. 7-4-37 Comp. 7-25-37

Shot or Treated. 5000 gal.

Contractor.

Issued. 10-9-37


County Reno.

CASING.

15 $\frac{1}{2}$ " 398'

85/8" 3305'

2 $\frac{1}{2}$ " tubing 3372'



Elevation. 1473

Production. Pot. 451 B.

116 B.W. flowed.

Figures indicate Bottom of Formations.

sand and shale	200
sand shale and shells	412
shale and shells	522
sand shale and shells	792
shale lime shells	1380
shale	1567
shale lime shells	1670
lime	1710
shale	1759
shale and shells	1930
shale	2000
lime	2033
shale and shells	2140
shale and lime	2195
lime	2285
shale and shells	2380
lime	2450
shale	2603
lime	2675
broken lime	2710
lime	2942
shale	2953
lime	2978
shale	2998
lime	3011
shale	3055
lime	3105
shale	3215
lime shale	3294
Chat Miss lime Top 3294	3374

Total Depth.

3294
1173
-1821