

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

THE CARTER OIL CO.
E. Hogan No. 5.


SEC. 19 T. 24 R. 4W
NW NE SW
330' fr N 957' fr EL SW $\frac{1}{4}$

County. Reno

Total Depth. 3390'
Comm. 5-6-37 Comp. 6-19-37
Shot or Treated. 1500 Gals. 3338-3390
Contractor. Carter Tools
Issued. 8-28-37 Rotary O-3348
Cable 3348-90

CASING:

10" 547'
8 5/8" 808'
5 3/16" 3346'



Elevation. 1473

Production. Pot. 404 B.
106 BW

Figures Indicate Bottom of Formations.

sand, shale, shells	666
shale & shells	741
shale	751
shale & shells	1080
sdv lime, shale & shells	1165
shale & shells	2014
shale	2040
lime	2070
shale	2094
lime & shale	2151
lime	2155
lime & shale	2209
lime, shale breaks	2261
shale & lime	2343
lime	2530
shale	2535
sand	2570
shale & shells	2696
lime	2740
lime & shale	2771
lime	2957
sdv lime	2985
lime	3014
shale	3025
shale & shells	3078
lime & shale	3109
lime	3145
lime & shale	3201
sdv lime	3225
shale	3257
shale & shells	3333
chat	3390
Total Depth.	

chat 3338-3390
1st pay 3368-3373
Last pay 3387-3390
1st gas 3354-3355
1st oil 3355-3357

3338
1473
-1865