

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

HAYNES DRLG. CORP.
Mueller No. 4.

SEC. 30 T. 24 R. 4W
NE SE NW
330' S 330' W of NESE NW

Total Depth. 3400'
Comm. 5-13-37 Comp. 6-7-37
Shot or Treated.
Contractor.
Issued. 8-7-37

County. Reno



CASING:

10³/₄"
7 "

551'
3345'

Elevation. 1475

Production. Pot. 509 B.

Figures Indicate Bottom of Formations.

surface sand & shale	150	shale	3108
shale	250	lime & shale	3136
shale & shells	368	lime	3154
shale & lime	461	shale & lime	3250
shale & salt	481	shale	3273
shale & shells	555	vari-colored shale	3291
shale, shells & sand streaks	633	shale	3330
lime & shale	877	vari-colored shale	3339
shale & shells	969	chat (Top chat 3343)	3350
salt	990	chert, chat white &	
shale	1010	shale lgt green	3356
lime	1071	small sh oil & very	
lime & shale	1193	small amt gas.	
lime	1223	chat & shale green	3361
brkn lime & shale	1247	shale green to brown	3366
red bed	1272	Well shows very sm amt gas	
shale	1289	chat & chert	3371
brkn lime & shale	1373	chat	3376
lime	1385	slight oil stain. Doubtful	
shale	1533	oil increase	
brkn lime & shale	1558	chat wtr	3383
shale	1625	chat no inc wtr	3390 ¹ / ₂
brkn lime	1653	chat	3396
shale	1689	white to lgt oil stain.	
shale & lime shells	1738	chat, pale green shale,	
lime & shale streaks	1792	and some chert	3400
lime	1824	white to lgt oil stain.	
shale	1847	Total Depth.	
brkn lime & shale	1866		
shale	1912		
lime & shale	1976		
shale	2040		
lime & shale	2065		
shale	2123		
lime brkn	2128		
lime & shale	2155		
shale	2252		
lime	2318		
lime & shale	2445		
shale	2495		
lime	2537		
sdv shale & lime	2571		
lime & shale	2637		
shale	2675		
lime	2707		
lime & shale	2761		
lime	2802		
lime & shale	2910		
lime	2956		
shale & shells	2980		
lime	2993		
lime hrd	3018		
brkn li. & sh. sdv sft	3041		
lime & shale	3095		

3343
1475
-1868