


IND. TERR. ILL. OIL CO.
Wm. Mueller No. 2.

SEC. 30 T. 24 R. 4W
CNL NE
330' S of N and 1324' E W of
NE $\frac{1}{4}$

Total Depth. 3376'
Comm. 4-22-37 Comp. 5-15-37
Shot or Treated.
Contractor. Olson Drlg. Co.
Issued. 7-24-37 Rotary & Cable.

County. Reno



CASING:
13" 280'
7" 3334'6"

Elevation. 1470

Production. Pot. 548 B.

Figures Indicate Bottom of Formations.

surface soil	15
sand	35
sand & clay	100
lime shells	156
shale & shells	620
brkn lime	720
shale & lime shells	831
brkn lime & shale	916
shale & shells	1108
brkn lime & shale	1190
lime	1220
lime & shale	1250
shale & shells	1394
brkn lime	1412
lime	1439
shale & shells	1623
shale	1660
lime	1680
brkn lime	1734
lime	1750
brkn lime	1790
shale & lime shells	1865
shale & shells	1974
brkn lime	2148
shale & lime shells	2187
brkn lime	2204
shale & shells	2280
brkn lime	2428
shale	2450
sdv shale	2495
shale & shells	2542
shale	2563
lime	2633
brkn lime	2663
lime	2708
brkn lime	27 45
lime	2973
porous lime	2975
lime	3067
show oil 2975-2979	
lime & shale	3104
brkn lime	3159
lime	3194
lime hrd	3221
brkn lime	3231
shale	3323
variegated shale	3333
chat	3376
sh gas 3336	
Total Depth.	

3333
1470
-1863