

KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

W. C. MCBRIDE, INC. ET AL.
Popp No. 1.


SEC. 32 T. 24 R. 4W.
SEc ME

Total Depth, 3882
Comm 10-5-34 Comp. 12-4-34.
Shot or Treated,
Contractor.
Issued, 1-5-35.

County, Reno.

CASING RECORD.

15 $\frac{1}{8}$ " 248 6" 3645' SIM UR 3867'
8" 3418' SIM corr.



Elevation, 1471

Production, DRY

Figures Indicate Bottom of Formations.

shale	230	shale	3366
shells	248	shale and lime shells	3425
shale and shells	713	Top of chat	3410
shale and shells	749	3423 $\frac{1}{2}$ equals 3421 derrick	
lime and shale	968	flocr, SIM.	
lime	1000	lime	3438
broken lime&shale	1042	chat	3472
shale and shells	1120	Hole reduced to 6"	3421.
lime	1148	water 3438-3443.	
shale & shells	1220	400' of water	3457
broken lime&shale	1290	chat	3492
broken lime	1345	2000' water	3492.
shale	1370	lime	3506
broken lime & shale	1560	chat	3515
shale and shells	1645	3000' water	3515
broken lime & shale	1715	sand and lime	3529
lime and shale	1860	chat	3538
shale & shells	1945	3533 equals 3541 corrected	
shale	1975	chat	3541
lime & shale	2048	lime	3549
shale and shells	2108	sand and lime	3557
lime	2162	lime	3575
shale and lime	2196	sand and lime	3593
shale & lime shells	2253	lime	3605
lime & shale breaks	2320	lime	3621
shale and lime	2345	carrying 3000' of wtr from	
shale & shells	2402	chat	
shale & brkn lime	2462	lime and sand	3629
lime	2591	lime	3660
shale & shells	2650	3660 equals 3645 SIM Corr,	
shale & lime	2685	lime brown	3672
lime top of lime	2737	Base Miss lime	3672 samples
broken lime & shale	2755	shale dark	3768
lime	2770	lime brown	3770
lime shells & sandy		Top Hunton lime	3768(samples)
shale	2783	500' water in one hour	3768-3770
lime	2790		
sdv lime	2810	lime	3775
broken lime	2830	500' water 1 hour	3769
sdv lime	2840	2500' water	3775
sdv shale and lime		shale and lime	3787
shells	2908	lime	3803
lime	3001	Base Hunton	3793 Samples.
shale & shells	3045	shale	3820
lime	3060	shale	3865
brkn lime & sand	3115	lime	3867
lime & brkn shale	3140	SLM 3867 equals	3873
lime & shale	3170	lime	3879
broken lime & shale	3217	sand (Wilcox)	3882.
lime	3241	HFV	3882
lime and shale	3263	Total Depth,	
lime	3270		
shale	3296	Top of K. C. lime	2675 Samples.
shale & lime shells	3330	Top of Chat	3410
		Top of Viola	3865'

3410
1471
-1939

3672
1471
-2201

3768
1471
-2297

3865
1471
-2394

3879
1471
-2408