

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-075-20262

KANSAS DRILLERS LOG

API No. 15 — 075 — 20,262
County Number

Operator
Dome Petroleum Corp.

Address
Suite 1500, 1600 Broadway Denver, Colo 80202

Well No. #1 Lease Name Spellman Burnett - Grisson


Footage Location
3300 feet from (S) line 1980 feet from (E) line

Principal Contractor **DNB Drilling Inc.** Geologist **Dick Konigsberg**

Spud Date 2-25-79 Total Depth 2550 P.B.T.D. 2530

Date Completed 4-5-79 Oil Purchaser

S. 4 T. 24 R. 40 W
Loc. 1980' FEL & 3300' FSL
C SW NE
County **Hamilton**
640 Acres



Locate well correctly
Elev.: Gr. 3314
DF _____ KB 3321

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	23#	358'	Class H	275	Cl H + 3% CaCl + flocele
Production	7-7/8"	4-1/2"	9.5#	2549'	Class H	450	4.5% gel + flocele Cl H + 18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3-1/8" csg gun	2443-2448

TUBING RECORD

	Setting depth	Packer set at
2-3/8"	2448'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/ 500 gal 15% HCl	2443-48
Frac'd w/ 20,000 gal 1/2 CO ₂ + 1/2 gelled 2% KCl wtr and 20,000# 10-20 sand and 10,000# 20-40 sand	2443-48

INITIAL PRODUCTION

Date of first production	Producing method (Flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 2-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Kansas Geological Survey, 3830 So. Meadline (P.O. Box 17027) Wichita, Kansas 67217.

100

Dome Petroleum Co.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

#1

Lease Name

Spellman

Testing poor gas producer

S 4 T 24 R 40E W

C SWNE

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Stone Corral	—	1936	Stone Corral	1936
Winfield	2430	2451	Winfield	2430

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Richard E. Whittenberg
Signature

Production Engineer
Title

8/9/79
Date

Date