

State Geological Survey  
**KANSAS DRILLERS LOG**  
 WICHITA BRANCH


**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.

S. 14 T. 21 R. 40 <sup>R</sup>/<sub>W</sub>

Loc. C NW 32 NE

County \_\_\_\_\_

640 Acres  
 N



MAY 18 1977

Elev.: Gr. 3222

DF \_\_\_\_\_ KB 3230

API No. 15 — 075 — 20,140  
 County Number

Operator  
 Computer Petroleum Exploration Co.

Address  
 1600 Broadway, Denver, CO 80202

Well No. 4 Lease Name  
 Thomeczek

Footage Location  
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Geologist  
 Wakefield Drilling R. Higginbottom

Spud Date Total Depth P.B.T.D.  
 9-9-76 2475 2445

Date Completed Oil Purchaser  
 TA

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8-5/8	20	316	Class H	275	3% CaCl
Production	7-7/8	4 1/2	9.5	2467	Class H	350	10% salt

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			1		2376-2394
<b>TUBING RECORD</b>			1		2332-2338
Size	Setting depth	Packer set at	1		2296-2300
TA					

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Acidized - Frac'd w/23,520 gals gelled 2% KCL +13,500# 20/40	2376-2394
Acidized w/500 gals	2332-2338
Acidized w/500 gals	2296-2300

**INITIAL PRODUCTION**

Date of first production TA	Producing method (flowing, pumping, gas lift, etc.)				
<b>RATE OF PRODUCTION PER 24 HOURS</b>	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) None		

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Computer Petroleum Exploration		DESIGNATE TYPE OF COMP.: OIL, G. DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Thomeczek	TA
S 14 T 24 R 40 E W		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite Sandstone Sandstone Lmy sandstone			Stone Corral Herrington Kriden Winfield	1867'(base) 2294' 2328' 2374'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>W. E. Babzale</i> Signature
	District Engineer Title
	February 7, 1977 Date