


IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 20 T. 24 R. 40 ^RW
Loc. C SE NW
County Hamilton



Locate well correctly
Elev.: Gr. 3210
DF _____ KB 3218

API No. 15 — 075 — 20,160
County Number

Operator
Computer Petroleum Exploration Co.

Address
1600 Broadway, Denver, CO 80202

Well No. 1 Lease Name Johnson

Footage Location
1265 feet from (N) $\frac{1}{8}$ line 1250 feet from $\frac{1}{8}$ (W) line

Principal Contractor Geologist
Wakefield Drl. Bob Higginbottom

Spud Date Total Depth P.B.T.D.
October 8, 1976 2425 2395

Date Completed Oil Purchaser
November 13, 1976 -

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8-5/8"	20	323	Class H	325	3% CaCl ₂
Production	7-3/4"	4 $\frac{1}{2}$ "	9.5	2426	Class H	500	10% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		2318-29

Size	Setting depth	Packer set at
2-3/8	2335'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/500 gals 15% Hcl	2318-29
Frac w/23,500 gals gelled 2% KCL Water	2318-29
+ 13,500# 20/40 sand	

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)
December 12, 1976 Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	-	110 MCF	35	- CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)
Shut-in pending market Upper Winfield

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

APR 1 8 1977

Operator

Computer Petroleum Exploration

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Johnson

Gas well

S 20 T 24 R 40 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Anhydrite
Sandstone
Sandstone
Sandstone - 1my

Stone Corral
Herrington
Kridet
Winfield

1810 (base)
2230'
2266'
2308'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

W. E. Babzale

Signature

District Engineer

Title

February 7, 1977

Date