

KANSAS DRILLERS LOG WICHITA BRANCH


API No. 15 — 075 — 20,288
County Number

S. 22 T. 24 R. 40 ^RW

Loc. C NESW

County Hamilton

640 Acres
N



Locate well correctly

Elev.: Gr. 3198

DF _____ KB 3206'

Operator
Dome Petroleum Corp.

Address
Suite 1500, 1600 Broadway Denver, Colo 80202

Well No. #3 Lease Name Overton

Footage Location
1980 feet from (S) line 1980 feet from (V) line

Principal Contractor Lakin Drilling Co. Geologist Dick Konigsberg

Spud Date 6/15/79 Total Depth 2450' P.B.T.D. _____

Completed 6/29/79 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	3 5/8"	23#	545'	Class "H"	400	3% CaCl + 1/2# floceie
Production	7 7/8"	4 1/2"	9.5#	2449'	Class "H"	400	4.5% Prehydrated gel + 1/2# floceie +
					Class "H"	150	18% salt, 1/2# floceie + 3/4 of 1% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF	3 1/8" csg gun	2340-44

Size	Setting depth	Packer set at
2 3/8"	2370'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/500 gal 15% Hcl acid	2340-44
Frac'd w/10,000 gal gelled 2% Kcl wtr, 12,000# 20/40 sd, 20,000# 10/20 sd & 4 1/2 tons CO ₂	2340-44

INITIAL PRODUCTION

Date of first production 6/29/79 Producing method (flowing, pumping, gas lift, etc.) Pumping - currently testing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	Testing MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Vented Producing interval(s) Winfield

INSTRUCTIONS: As provided in KCC Rule 2-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 67217. Identical copies will be on file in the Oil and Gas Division, Lawrence, Kansas.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Dome Petroleum Corp.

Well No.

Lease Name

Gas

#3

Overton

S 22 T 24 R 40 W

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Stone Corral (Anhydrite)

1820

Stone Corral

1820

Winfield (Sd)

2322

Winfield

2322

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Richard E. Hesterberg
Signature

Production Engineer

Title

October 18, 1979

Date

DRILLER'S LOG

DOME PETROLEUM CORP.
No. 3 Overton
C NE SW
Sec. 22-24S-40W
Hamilton Co., Ks.

Commenced: 6-15-79
Completed: 6-19-79

Surface Casing: 536' of 8-5/8"
cmtd w/400 sx Class H, 3% cc

FORMATION

DEPTH

Surface Hole	0 - 545
Sand & Shale	545 - 605
Shale & Sand	605 - 1625
Sand & Shale	1625 - 2325
Shale	2325 - 2450 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
James L. Donelson *Reg. E.P.*

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 21st day of June, 1979.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Lawick County, Kansas
My Aopt. exp. April 30, 1980