

KANSAS DRILLERS LOG
WICHITA BRANCHAPI No. 15 — 075 — 20,290
County Number

Operator

Dome Petroleum Corp.

Address

Suite 1500, 1600 Broadway Denver, Colo 80202

Well No.

5

Lease Name

Wood

Footage Location

1980

feet from (N) (S) line

1980

feet from (E) (W) line

Principal Contractor

DNB Drilling, Inc.

Geologist

Dick Konigsberg

Spud Date

6/21/79

Total Depth

2450'

P.B.T.D.

Date Completed


7/8/79

Oil Purchaser

S. 29 T. 24 R. 40 W

Loc. C SWNE

County Hamilton

640 Acres
N

Locate well correctly

Elev.: Gr. 3257

DF KB 3265

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8 5/8"	23#	542'	Class "H"	400	3% CaCl + $\frac{1}{4}$ # D29
Production	7 7/8"	4 $\frac{1}{2}$ "	9.5#	2444'	Class "H"	400	4 $\frac{1}{2}$ % Prehydrated gel $\frac{1}{4}$ # floccle +
					Class "H"	150	18% Salt, 3/4 of 1% CFR-2 + $\frac{1}{4}$ # floccle

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF	3 1/8" gun	2343-2347
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	2358'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/500 gals 15% Hcl	2343-47
Frac'd w/10,000 gals 2% gelled Kcl wtr, 50 tons CO ₂ , 12,000#	
20/40 sd & 20,000# 10/20 sd.	2343-47

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
7/11/79	Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	526	30	bbls. CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	
Vented			Winfield	

INSTRUCTIONS: As provided in KCC Rule 2-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 67212. Drillers Logs will be on open file in the Oil and Gas Division, Lawrence, Kansas.

29-24-40W

Stone Corral (Anhydrite)		1826	Stone Corral	1826
Winfield (Sd)	2327		Winfield	2327

DRILLER'S LOG

DOME PETROLEUM CORP.
No. 5 Wood
C SW NE Sec. 29-24S-40W
Hamilton Co., Ks.

Commenced: 6-19-79
Completed: 6-24-79

Surface Casing: 532' of 8-5/8"
cmted w/400 sx Class H, 3% cc

FORMATION

DEPTH

Surface Hole	0 - 542
Sand	542 - 1130
Sand & Shale	1130 - 1695
Shale & Sand	1695 - 2145
Sand & Shale	2145 - 2450 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 26th day of June, 1979.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983