

PT

KANSAS
State Geological Survey
WICHITA, BRANCH

**WELL COMPLETION REPORT AND
DRILLER'S LOG**


API No. 15 — 075 — 20,306 ✓
County Number

S. 31 T. 24S R. 40 W

Loc. C NW NW

County Hamilton

Operator Dome Petroleum Corp.			
Address 1600 Broadway, Suite 1400, Denver, Colorado 80202			
Well No. 2	Lease Name Levens		
Footage Location 660 feet from (N) XSE line 660' feet from XSE (W) line			
Principal Contractor DNE Drilling, Inc.		Geologist Dick Konigsberg	
Spud Date 3-12-80	Date Completed 3-17-80	Total Depth 2,475'	P.B.T.D. 2,460'
Directional Deviation N/A		Oil and/or Gas Purchaser Sunflower Electric	



Locate well correctly
Elev.: Gr. 3,285'

DF KB 3,293'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	566'	Class "H"	450	3% CaCl + 1/4 #/sk flocele
Production	7-7/8"	4-1/2"	9.5#	2470'	Class "H"	400	4.5% pre-hydrated gel, 1/2 #/sk flocele

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF (14)	3-1/8" csg gun	2392'-2400'

TUBING RECORD		
Size	Setting depth	Packer set at
2-3/8"	2431'	N/A


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized with 500 gals 15% HCl	2392'-2400'
Frac'd with 20,000 gals fluid, 1/2 gelled 2% KCl water & 1/2 CO ₂ , with 12000# 20/40 sd & 20,000# 10/20 sd.	2392'-2400'

INITIAL PRODUCTION

Date of first production 4-12-80		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls.	Gas 427 MCF	Water 30 bbls.	Gas-oil ratio N/A	CFPB
Disposition of gas (vented, used on lease or sold) Vented (Well shut in)			Producing interval (s) 2392'-2400'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Dome Petroleum Corp.		DESIGNATE TYPE OF COMPLETION: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 2	Lease Name Levens	Gas	
S. 31 T. 24S R. 40 W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Base Stone Corral		1880'	B. Stone Corral
Top Herrington	2302'		T. Herrington
Top Krider	2336'		T. Krider
Top Winfield	2381'		T. Winfield
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Production Supervisor Title April 29, 1980 Date		

PT

31- 24- 40W

DRILLER'S LOG

DOME PETROLEUM CORP.
No. 2 Levens
C NW NW
Sec. 31-24S-40W
Hamilton Co., Ks.

Commenced: 3-12-80
Completed: 3-17-80

Surface Casing: 556' of 8-5/8"
cemented w/450 sx common, 3% cc

FORMATION

DEPTH

Surface Hole	0 - 566
Sand & Shale	566 - 766
Shale & Sand	766 - 1520
Sand & Shale	1520 - 1797
Shale	1797 - 2180
Shale & Lime	2180 - 2375
Shale	2375 - 2475 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 20th day of March, 1980.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983