


90178

12-195W MAP NO. K-79 SEC. 6-24S-41W
 STATE Kansas COUNTY Hamilton LOC. App C N/2 of Sec
 OPER. Anadarko Production Company - Liberal, Kansas FT/FR _____ LINE _____
 WELL #1 FARM Millsap "A" FT/FR _____ LINE _____
 BRADSHAW ELEV. 3273 GR. 3281 DF. 3284 KB _____
 WAKEFIELD DRILLING GEOL. Will Sharp
 CONT. 2400' Winf Test
 CO. _____
 INT. _____
 FR. 11-25-64 SPUD. 11-24-64 COMP. 12-22-64
 TD. 2304 FM. Winf PBD. _____
 PRODUCING FM. FROM — TO PERF W/HOLES TREATMENT
 Winf 2284 (only) 4 1000A & Frac
 124 hr BD 1,788,000 CFCPD SIP 430#

Completion Record

Casing Record

10-3/4" @661' w/600 Sx. 24" @35' w/4 yds cem
 4 1/2" @2302' w/125 Sx. 2-3/8" @1121' w/500 Sx.



Data Inc.

(GR Log Tops:) RTD 2304, Log 4 1/2" @2302' w/125 Sx., 2-3/8"
 B/Cimm 1800 #1473 @ 1121' w/500 Sx., Perf 4/2284 (Winf),
 Winf 2271 #1002 1000A (3%) Frac 15,000 GW x 4000# sd x
 LTD 2303 # 970 200,304 CF CO-2, 13 hr SIP 430#, 10 hr BD
 RTD 2304 # 969 2,289,000 CFCPD, decline to 1,788,000
 CFCPD, 1 1/2" tbg @2285, 24 hr blo dn Ga
 1,788,000 CFCPD, SIP 430#/13 hrs, Winf

ok asopick

@2284, (Will dispose SW in Glor thru 2-3/8" tbg later) -COMPLETED
 12-15-64