


90175

10-47W MAP NO. \_\_\_\_\_ REPL. COMP. SEC. 3-24S-41W  
 STATE Kans COUNTY Hamilton LOC. C NE NE  
 OPER. Anadarko Production Co. - Liberal, Kansas FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 WELL 1 FARM Boltz "A" FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
Bradshaw Field ELEV. 3288 GR. 2-5 3294 DF 3297 KB  
 CO. E. F. Wakefield GEOL. John Kimberly  
 INT. 2375' Gas Test  
 F.R. 9-8-64 SPUD. 9-10-64 COMP. 10-6-64  
 TD. 2369 FM. Winfield PBD. 2362  
Winf 2354 (only) 4 way jet 250A & Frac  
4 Pt OF Ga 3,110,000 Cfgpd, SIP 455#  
10 3/4" @699 w/300 sx. 4 1/2" @2367 w/150 sx.



Data Inc.

(GR Log) RID 2368, Log  
 B/Cim 1641 / 1647 WLT #1 (RC) 1906-09, Op 1 hr, R 330,000  
 Winf 2338 / 950 cc filt wtr, SP less than 100#, FSIP  
 LTD 2369 / 919 850#/20", 4 1/2" @2367 w/150 sx. - 2 3/8"  
 RTD 2368 / 920 @1157 w/500 sx., CO 2362 PBD, 4 way  
 jet @2354 (Winf), Ga 120,000 Cfgpd, nat  
 Frac 10,000 GA x 4000# sd x 200# hulls x 170,000 cu ft of CO-2,  
 20 hr BD, Ga 3,253,000 Cfgpd, 1 1/4" tbg @2339, 4 Pt OF Ga 3,100,000  
 Cfgpd, SIP 455#/44 hrs, Winf @2354 = COMPLETED (9-28-64)  
 REPLACEMENT COMPLETION (10-27-64) Corrected Co Ga

CSO