

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR F & M OIL CO., INC.

API NO. 15-185-21,404

ADDRESS 422 Union Center

COUNTY Stafford

Wichita, Kansas 67202

FIELD _____

**CONTACT PERSON Preston Burkey

PROD. FORMATION _____

PHONE Mobile # 913-483-5295

LEASE Schritter

PURCHASER _____

WELL NO. 1

ADDRESS _____

WELL LOCATION SE SW SW

DRILLING Union Drilling Co., Inc.

_____ Ft. from _____ Line and

CONTRACTOR _____

_____ Ft. from _____ Line of

ADDRESS 422 Union Center

the SEC. 32 TWP 25S RGE. 12W

Wichita, Kansas 67202

PLUGGING Sun Oil Well Cementing, Inc.

CONTRACTOR _____

ADDRESS Box 169

Great Bend, Kansas 67530

TOTAL DEPTH 4305' PBTD _____

SPUD DATE 10-23-81 DATE COMPLETED 11-8-81

ELEV: GR 1880 DF _____ KB 1889

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

(New) / (Used) casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	20#	312'	common	250	2% gel, 3% CC


LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at



WELL PLAT

KCC _____
KGS ☒
MISC _____
(Office Use)

Name of lowest fresh water producing stratum Unkown Depth Unkown 85617

Estimated height of cement behind Surface Pipe To Surface.

DV USED? None

WELL LOG

32-25-12W

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
DST# 1 3776-380', 30-45-30-45, rec 2000' GIP, 150' HO&GCM, 120' HO&GCMW, 120' GCW, IFP 91-128#, ISIP 1229#, FFP 164-183#, FSIP 1156#.			Sample Tops:	
			Topeka	3120 (-1231)
			Heebner	3447 (-1558)
			Toronto	3466 (-1577)
			Doug Sh	3485 (-1596)
			Doug Sd	3511 (-1622)
			Br/Lime	3610 (-1721)
			Lansing	3635 (-1746)
			B/KC	3945 (-2056)
			Miss	4040 (-2151)
DST# 2 3803-42', 30-30-30-30, wk blow throughout, rec 120' SGCMW, IFP 82-100#, ISIP 1082#, FFP 119-119#, FSIP 1036#.			Electric Log Tops:	
			Topeka	3120 (-1231)
			Heebner	3446 (-1557)
			Toronto	3464 (-1575)
			Doug Sh	3483 (-1594)
			Doug Sd	3508 (-1619)
			Br/Lime	3608 (-1719)
			Lansing	3634 (-1745)
			B/KC	3942 (-2053)
			Miss	4045 (-2156)
			Viola	4139 (-2250)
			Simp Sh	4193 (-2304)
			Simp Sd	4197 (-2308)
			Arbuckle	4286 (-2397)
			RTD	4305 (-2416)
DST# 3 3849-82', miss-run, tool would not get to bottom.				
DST# 4 3849-82', 30-30-30-30, wk bldg blow on 1st open & 2nd open, rec 140' GIP, 20' G&SOCMW, 80' GCMW, IFP 73-82#, ISIP 1091#, FFP 100-109#, FSIP 1000#.				
DST# 5 4040-77', 30-45-60-45, fr bldg blow on 1st & 2nd opens, rec 180' GIP, 60' GCM, IFP 73-64#, ISIP 91#, FFP 73-73#, FSIP 91#.				

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS, _____

E. A. Falkowski OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (FOR)(OF) F & M OIL CO., INC.

OPERATOR OF THE Schritter LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 8th DAY OF November, 19 81 AND