

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

25-25-13W

Company- D.R. LAUCK OIL CO., INCC & SUNRAY MID-

SEC.

25 T. 25

R. 13W

Farm- Russell Estate No. 1 CONTINENT OIL CO.

SW SW NE

Total Depth. 4616'

Comm. 6-2-56

Comp. 6-18-56

Shot or Treated.


Contractor. 4-6-57

Issued. 4-6-57

County

Stafford

KANSAS



Elevation. 1901' DF

Production. Dry

CASING:

8 5/8" 229' w/ 205 sx cem.

Figures indicate Bottom of Formations.

red bed-shells 229  
 red bed 235  
 sdy lime 243  
 red bed-shells 285  
 red bed 740  
 Anhydrite 770  
 shale-shells 1300  
 salt-shale 1340  
 shale-shells 1660  
 shale-lime 2600  
 lime 2615  
 shale-shells 2790  
 shale-lime 3125  
 lime 3330  
 shale-lime 3450  
 lime 3540  
 lime-shale 3665  
 lime 3972  
 lime-shale 4072  
 lime-shale-chert 4087  
 chert 4154  
 shale-chert 4175  
 sand-shale 4190  
 shale-chert 4200  
 shale 4229  
 Arbuckle 4245  
 Arbuckle cherty 4320  
 Arbuckle 4616  
 Total Depth RTD.

DST #1 - (M-D) 4052-4072' Open 30 min.;  
 weak blow 7"; rec. 20' mud IFP O#;  
 FFP O#; BHP O# in 20 min.

DST #2 - (W) 4088-4098' Open 1 hr.;  
 weak blow 1 hr.; rec. 100' muddy salt  
 wtr.; IFP O#; FFP O#; BHP 1220# in  
 30 min.

DST #3 - (M-D) 4180-4190 Open 30 min.;  
 weak blow 6 min.; rec. 15' mud IFP O#;  
 FFP O#; BHP O# in 20 min..

TOPS: Sample Schl.  
 Anhydrite (scout) 740  
 Heebner 3466 3456  
 Brown lime 3613 3621  
 Lansing 3635 3638  
 Kansas City 3916 3914  
 Mississippian 4050 4044  
 Viola 4087 4088  
 Simpson shale 4169 4154  
 Arbuckle 4224 4226