


Total Depth. 4145'
Comm. 3-13-40 Comp. 4-6-40
Shot or Treated.
Contractor.
Issued. 6-29-40



CAS ING:
10 3/4" 457'
7 " 4099'

Elevation.

Production. Pot.3910 B.Echo.

Figures Indicate Bottom of Formations.

cellar	5'10"
surface clay & sand	85
red bed & red clay	460
red bed, shale, shells	580
red bed & shale	730
anhydrite	765
shale	885
shale & shells	1253
salt, shale, shells	1525
salt & shale	1580
shale & lime	1925
lime sdy	2000
shale blue	2050
shale	2060
sand	2102
shale & shells	2190
shale & lime	2405
shale & brkn lime	2520
shale & lime	2730
shale & brkn lime	2935
shale	2975
lime brkn	3015
shale & shells	3055
shale & lime shells	3090
lime	3435
shale & lime	3530
shale & lime shells	3540
lime	3635
lime sdy	3685
shale & lime	3730
lime	3734
lime brkn	3754
lime	3890
shale & chert shells	3921
lime & chert	3958
shale & chert shells	3985
chert	3993
lime cherty	4035
lime	4055
Simpson sand	4068
lime	4084
shale & sand	4100
Arbuckle	4108 1/2
lime	4145
Total Depth.	

Top Arbuckle 4097

Total Depth from cement
floor 4144