

Plotted E.C.K.


12-25-13W

CONTINENTAL OIL CO.
P. Mather No. 1

SEC. 12 T. 25 R. 13W.
SEc NW
330' N 330' W of Center.

Total Depth, 4125
Comm. 3-30-39 Comp. 4-30-39
Shot or treated, No acid.
Contractor, Parker Drlg. Co.
Issued, 8-19-39

County Stafford.



CASING.

103/4" 464'
7" 4079'

Elevation.

Production, Pot. 2939 B.

Figures Indicate Bottom of Formations.

cellar	10'8	shale & shells	3548
surface soil	30	brokon limo	3560
sand and clay	130	limo	3580
red bed and shale	350	limo soft	3590
red bed and sand	405	limo	3615
shale and shells	500	limo donso	3629
sand and shale	540	limo	3635
red bed and shale	735	chorty limo	3640
anhydrite	760	limo	3643
shale and shells	1240	limo brokon	3667
salt shells and shale	1460	limo donso	3693
shale and salt	1590	limo soft	3698
lime shells	1600	limo donso	3722
shale	1640	limo soft	3727
broken lime	1690	limo	3735
shale	1720	limo soft	3745
broken lime	1750	limo donso	3765
broken lime and shalo	1845	limo soft	3774
brokon limo	2033	limo donso	3794
limo soft and sand	2084	chorty limo donso	3808
brokon limo	2105	shale and lime	3814
brokon limo and shalo	2190	broken lime and shale	3876
broken limo	2430	broken lime & cherty	3896
shalo and shells	2543	chert	3905
broken lime	2558	cherty lime	3928
shale and shells	2625	lime hard	3934
broken lime	2665	lime hard and chert	3957
shale and shells	2680	cherty lime	3975
broken lime	2690	lime & cherty	4011
shale and shells	2740	cherty lime	4020
lime	2755	lime and shale	4035
shale and shells	2775	sand	4050
broken lime	2790	lime and shale	4055
shale and shells	2805	shale	4079
broken lime	2846	lime rough	4082
shale and shells	2860	lime	4093
shale	2870	lime hard	4100
limo and shale	2890	lime	4103
lime	2915	lime hard	4123
brokon limo	2930	lime	4125
shale and shells	2975		
brokon limo	3010	Total Depth.	
shalo and shells	3062		
brokon limo soft	3102	Top Arbuckle lime from cement floor level	4076
donso limo	3127		
lime brokon soft	3134	Total depth from cement floor level	4124
lime mod	3160		
lime donso	3185	Total fill up with oil	3975'
limo	3210	5-4-39 On initial potential test the well pumped	
limo soft	3218	979.70 bbls of oil in 8 hours, giving the well a	
limo	3238	24 hour potential of 2939 bbls of oil no water.	
lime broken	3296	Nat. no acid used.	
lime donso	3310		
lime brokon	3340		
lime dense	3405		
broken lime	3431		
shale and lime shells	3512		